



Project Manual


City of Danville

City Auditorium Roof Replacement Project

125 North Floyd Street, Danville, VA 24541

IFB No. 18-19-014

August 17, 2018



Submitted By:

Dewberry
551 Piney Forest Road
Danville, Virginia 24540
434-797-4497

TABLE OF CONTENTS

INVITATION FOR BIDS
GENERAL CONDITIONS
SCOPE OF WORK
SUPPLEMENTAL GENERAL CONDITIONS
BID PROPOSAL

SPECIFICATIONS

011000	SUMMARY	011000-1
012200	UNIT PRICES	012200-1
012500	SUBSTITUTION PROCEDURES	012500-1
012600	CONTRACT MODIFICATION PROCEDURES	012600-1
012900	PAYMENT PROCEDURES	012900-1
013100	PROJECT MANAGEMENT AND COORDINATION	013100-1
013200	CONSTRUCTION PROGRESS DOCUMENTATION	013200-1
013300	SUBMITTAL PROCEDURES	013300-1
015000	TEMPORARY FACILITIES AND CONTROLS	015000-1
016000	PRODUCT REQUIREMENTS	016000-1
017300	EXECUTION	017300-1
017419	CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL	017419-1
017700	CLOSEOUT PROCEDURES	017700-1
017839	PROJECT RECORD DOCUMENTS	017839-1

TECHNICAL SPECIFICATIONS

061000	ROUGH CARPENTRY	061000-1
075323	ETHYLENE-PROPYLENE-DIENE-MONOMER (EPDM) ROOFING	075323-1
076200	SHEET METAL FLASHING AND TRIM	076200-1

DRAWINGS

A1.01	CITY AUDITORIUM ROOF PLAN
A1.02	DETAILS

END OF TABLE OF CONTENTS



City of Danville, Virginia

PO Box 3300
Danville, VA 24543

427 Patton Street, Rm 304
Danville, VA 24541

J. Gary Via, CPPO
Director of Purchasing
e-mail: viajg@danvilleva.gov

Phone: (434) 799-6528
Fax: (434) 799-5102
e-mail: purchasing@danvilleva.gov

INVITATION FOR BID

Bid No.: IFB 18-19-014

Title: City Auditorium Roof Replacement Project

Pre Bid Conference: A Pre Bid Conference will be held September 14, 2018 at 10:00 a.m. in the conference room at 125 North Floyd Street, Danville, VA 24541

Bid Closing Date: Sealed Bids shall be accepted no later than September 27, 2018 at 2:00 p. m. at the Purchasing Department, 427 Patton Street, Room 304, Danville, VA 24541

Direct Inquires to: J. Gary Via, Director of Purchasing
(434) 799-6528 option 4

TABLE OF CONTENTS

1.0	General Conditions
2.0	Scope of Work
3.0	Supplemental General Conditions
PP1	Bid Proposal and Required Submittal Pages
	Project Manual as prepared by Dewberry

IFB 18-19-014

“City Auditorium Roof Replacement Project”

1.0 GENERAL CONDITIONS

1.1 Intent: Secure Virginia-licensed contractor to replace the roofing at the City Auditorium on 125 North Floyd Street, Danville, VA 24541. Remove existing EPDM roofing system to existing deck and provide a new 60 mil EPDM membrane roof system as described in the contract documents.

1.2 Sealed bids must be received in the Purchasing office no later than 2:00 p.m., September 27, 2018, mail to:

City of Danville
J. Gary Via
Purchasing Department
427 Patton Street, Room 304
Danville, VA 24541

1.3 Pre bid Conference: A pre-bid conference will be held on September 14, 2018 at 10:00 a.m. in the conference room, 125 North Floyd Street, Danville, VA 24541.

1.4 Bonds: 5% Bid bond; 100% performance and payment bonds.

1.5 Time of Completion: Ninety (90) calendar days.

1.6 Liquidated Damages: Three hundred (\$300.00) dollars per calendar day.

1.7 Project Manager for the City: Walter Lucas; Public Works. 434.799.5245

1.8 Code: All work performed shall conform to the Virginia Uniform Building Code.

1.9 Retainage: In making payments, there shall be retained five percent (5%) of the estimated amount until final completion and acceptance of the contract work.

2.0 SCOPE OF WORK

2.1 The Contractor shall provide all labor, material, equipment, supervision, & incidentals to perform work as detailed in Project Manual and plans as prepared by Dewberry dated August 17, 2018 (attached).

3.0 SUPPLEMENTAL GENERAL CONDITIONS

3.1 Compliance: The Contractor shall comply with the provisions of the following:

The City of Danville’s “Standard Requirements & Instructions for Bidding”, Version 1.4, dated May 22, 2008. Copies may be obtained from the Purchasing

Office or by downloading from the City's website "Finance Department, Purchasing Division.

3.2 Award

- A. The award will be made to the lowest responsible and responsive bidder, with consideration given to completion time.
- B. The City reserves the right to reject any or all offers and to waive informalities and minor irregularities in offers received.

3.3 Authority

- A. The Director of Purchasing as the designee of the City Manager has the sole responsibility and authority for negotiating, placing, and when necessary modifying each and every invitation to bid, purchase order or other award issued by the City of Danville. In the discharge of these responsibilities, the Director of Purchasing may be assisted by assigned buyers. No other City officer or employee is authorized to order supplies or services, enter into purchase negotiations, or in any way obligate the government of the City of Danville for any indebtedness. Any purchases contrary to these provisions and authorities shall be void and the City shall not be bound thereby.
- B. This procurement process, including withdrawal of bids and appeal or protests, is governed by the "PROCUREMENT CODE OF THE CITY OF DANVILLE, VIRGINIA". Copies of the Procurement Code may be obtained by writing the City of Danville Purchasing Department, 427 Patton St. Room 304, Danville, Virginia 24541 and by downloading from the City's website, Finance Department, Purchasing Division. The City of Danville does not discriminate against faith-based organizations.

3.4 Bid Preparation

- A. Bid proposals must be written in ink or typewritten and shall be submitted on the forms issued. Unsigned or qualified bids will not be accepted. No bid may be considered if received after the time shown on Title Page. Contractors are expected to examine all instructions, specifications, drawings, sites, installations, etc. Failure to do so will be at the Contractor's risk. Erasures or other changes must be initialed by the person signing the bid.
- B. Envelopes containing bids must be sealed and marked in the lower left hand corner IFB 18-19-014 "City Auditorium Roof Replacement Project" and submitted to the office indicated on title page.

C. SCC Number

Contractors organized as a stock or nonstock corporation, limited liability company, business trust, or limited partnership or registered as a registered limited liability partnership shall be authorized to transact business in the Commonwealth as a domestic or foreign business entity if so required by Virginia Title 13.1 or Title 50 or as otherwise required by law. A Contactor organized or authorized to transact business in the Commonwealth pursuant to Virginia Title

13.1 or Title 50 shall include in its bid or proposal the identification number issued to it by the State Corporation Commission. Any bidder or offeror that is not required to be authorized to transact business in the Commonwealth as a foreign business entity under Title 13.1 or Title 50 or as otherwise required by law shall include in its bid or proposal a statement describing why the bidder or offeror is not required to be so authorized

3.5 Bidder Eligibility

- A. Bidders are required to submit evidence that they have practical knowledge of the particular work bid upon and that they have the financial resources to complete the proposed work. Failure on the part of any Bidder to carry out previous contracts satisfactorily, or lack of experience or equipment necessary for the satisfactory and timely completion of this Project, may be deemed sufficient cause for disqualification of said Bidder.
- B. The Bidder must readily and independently document that the Bidder possesses the experience, equipment and financial resources necessary for a timely and professional completion of this project.
- C. Irregular Bid Proposals: Bid proposals shall be considered irregular for the following reasons:
 - 1. If the bid is on a form other than that furnished by the City, if the City's form is altered, or if any part of the proposal form is detached.
 - 2. If there are unauthorized additions, conditional or alternate pay items, or irregularities of any kind which make the proposal incomplete, indefinite, or otherwise ambiguous.
 - 3. If the bid does not contain a unit price for each pay item listed in the proposal.
 - 4. If the bid contains unit prices that are obviously unbalanced.
 - 5. If the bid is not accompanied by the proposal guaranty specified by the City.
- D. Withdrawal of Bid Due to Error:
 - 1. A bidder for a City construction contract, other than a contract for construction or maintenance of public highways, may withdraw his bid from consideration, if the price bid was substantially lower than the other bids due solely to a mistake therein, provided the bid was submitted in good faith and the mistake was a clerical mistake, as opposed to a judgment mistake, and was actually due to an unintentional arithmetic error or an unintentional omission of a quantity of work, labor, or material made directly in the compilation of the bid, which unintentional arithmetic error or unintentional omission can be clearly shown by objective evidence drawn from inspection of original work papers, documents, and materials used in the preparation of the bid sought to be withdrawn.
 - 2. The bidder shall give notice in writing of his claim of the right to withdraw his bid within two (2) business days after the conclusion of the bid opening procedure.

- E. Disqualification of Bidder: A bidder shall be considered disqualified for any of the following reasons:
1. Submitting more than one proposal from the same partnership, firm, or corporation under the same or different name.
 2. Evidence of collusion among bidders. Bidders participating in such collusion shall be disqualified as bidders for any future work of the City until any such participating bidder has been reinstated by the City as a qualified bidder.
 3. If the bidder is considered to be in “default” for any reason specified in §5.4.

3.6 Bids Binding 60 Days

Unless otherwise specified, all formal bids submitted shall be binding for sixty (60) calendar days following bid-opening date.

3.7 Cleanup

- A. The Contractor at all times shall keep the premises free from accumulation of waste materials or rubbish caused by his operations. At the completion of the work, he shall remove all his waste materials and rubbish from and about the project as well as all his tools, construction equipment, machinery, and surplus materials.
- B. If the Contractor fails to clean up at the completion of the work, the City may do so and the cost thereof shall be charged to the Contractor.

3.8 Control of Work

- A. On all questions relating to quantities, the acceptability of materials and equipment, or work, and the interpretation of the Contract Documents, the decision of the Project Manager is final and binding, and shall be precedent to any payment under the contract.
- B. All work and material are subject to the inspection and approval of the Project Manager. Any work done without proper inspection will be subject to rejection. Inspection of the work shall not relieve the Contractor of the obligation to fulfill all conditions of the contract. The Project Manager may require the Contractor to remove from the work any employee, as the Project Manager may deem incompetent, careless or insubordinate.
- C. Certain items of work may be performed by forces of the City. The Contractor shall cooperate fully in scheduling and coordinating with the Project Manager such that no delay will result in the performance of such work. If the Contractor claims that such work delays or causes additional costs, he shall make claims as provided in Work Changes.
- D. The City may award, or may have awarded contracts to others for other work. The Contractor shall cooperate fully with such other Contractors by scheduling his own work with that to be performed under other Contracts as may be directed

by the City. The Contractor shall not commit or permit any act which will interfere with the performance of work by any other Contractor as scheduled.

- E. Neither the final certificate of payment nor any provision in the contract documents, nor partial or entire occupancy of the premises by the City, shall constitute an acceptance of work not done in accordance with the contract documents or relieve the Contractor of liability in respect to any express warranties or responsibility for faulty materials or workmanship. The Contractor shall remedy any defects in the work and pay for any damage to other work resulting therefrom, which shall appear within a period of one year from the date of final acceptance of work unless a longer period is specified. The City will give notice of observed defects with reasonable promptness.

3.9 Equal Employment

During the performance of this contract, the Contractor agrees as follows:

- A. The Contractor will not discriminate against any employee or applicant for employment because of race, religion, color, sex, or national origin, except where religion, sex, or national origin is a bona fide occupational qualification reasonably necessary to the normal operation of the Contractor. The Contractor agrees to post in conspicuous places, available to employees and applicants for employment, notices setting forth the provisions for this non-discrimination clause.
- B. The Contractor also shall not discriminate against any handicapped person in violation of any state or federal law or regulation and shall also post in conspicuous places, available to employees and applicants for employment, notices setting forth the provisions of this additional non-discrimination clause.
- C. The Contractor, in all solicitations or advertisements for employees placed by or on behalf of the Contractor, will state that such contractor is an equal opportunity employer.
- D. Notices, advertisements, and solicitations placed in accordance with Federal law, rule or regulation shall be deemed sufficient for the purpose of meeting the requirements of this section.
- E. The Contractor will include the provisions of the foregoing paragraphs in every subcontract or purchase order over \$10,000 so that the provisions will be binding upon each subcontractor or vendor.
- F. The Contractor will otherwise comply with all other applicable provisions of local, State, and Federal law.

3.10 Drug Free Work Place

During the performance of this contract, the contractor agrees to:

- A. Provide a drug-free workplace for the contractor's employees.
- B. Post in conspicuous places, available to employees and applicants for employment, a statement notifying employees that the unlawful manufacture,

sale, distribution, dispensation, possession, or use of a controlled substance or marijuana is prohibited in the contractor’s workplace and specifying the actions that will be taken against employees for violations of such prohibition.

- C. State in all solicitations or advertisements for employees placed by or on behalf of the contractor that the contractor maintains a drug-free workplace.
- D. Include the provisions of the foregoing clauses in every subcontract or purchase order of or over \$10,000, so that the provisions will be binding upon each subcontractor or vendor.

“Drug-free workplace” means a site for the performance of work done in connection with a specific contract awarded to a contractor in accordance with this chapter, the employees of whom are prohibited from engaging in the unlawful manufacture, sale, distribution, dispensation, possession or use of any controlled substance or marijuana during the performance of the contract.

3.11 Guaranty

- A. The Contractor shall guarantee that all the materials used and all the work done under the contract shall fully comply with the requirements of the plans and specifications and the instructions of the City.
- B. All expenses covering return or replacement of defective or improper equipment or merchandise will be assumed by the Contractor. In no instance shall the contractor refer the City to any distributor or manufacturer for settlement of any claim arising from defective or improper equipment or merchandise. If the Contractor shall fail to replace or repair any defective or improper equipment or merchandise within thirty (30) days from date of notice, the City may make the necessary corrective arrangements and charge the cost to money due the Contractor or bill the Contractor. The Contractor agrees to reimburse the City in such instances. Samples of any warranties which will apply to the goods being offered for sale shall be included as part of the bid.
- C. Any defects in the completed work or failure of the construction to fully perform or endure the service for which it is intended, which in the opinion of the City are caused by or due to the use of materials, skill or workmanship not in compliance with the said plans, specifications and instructions, that may appear in the work within a period of twenty-four (24) months after acceptance by the City shall be regarded as prima facie and conclusive evidence that the Contractor has failed to comply with the said specifications, plans, and instructions. The Contractor in this event shall at his own expense, at such time and in such manner as the Engineer may direct, repair or take up and reconstruct any such defective work, in full compliance with the original specifications, plans, and instructions. The repairs required to be made by the Contractor shall extend only to making good an inherent defects which become manifested in the materials and workmanship under ordinary conditions, and shall not be held to cover any breakage or damage caused by improper use or by accident resulting from circumstances over which the Contractor has no control.

3.12 Indemnification

- A. The Contractor shall indemnify, keep and save harmless the City, its agents, officials and employees, against all injuries, deaths, loss, damages, claims, patent claims, suits, liabilities, judgments, costs and expenses, which may in anywise accrue against the City, its agents, officials and employees in consequence of the granting of this contract or which may in anyway result therefrom, whether or not it shall be alleged or determine that the act was caused through negligence or omission of the Contractor or his employees, or of the subcontractor or his employees, if any, and the Contractor shall, at his own expense, appear, defend and pay all charges of attorneys and other expenses arising therefrom or incurred in connection therewith, and, if any judgment shall be rendered against the City in any such action, the Contractor shall, at his own expense, satisfy and discharge the same. The Contractor expressly understands and agrees that any performance bond or insurance protection required by this contract, or otherwise provided by the Contractor, shall in no way limit the responsibility to indemnify, keep and save harmless and defend the City, its agents, officials, and employees as herein provided. The Contractor shall have charge and control of the entire work until its completion and acceptance by the City.
- B. The Contractor shall assume all risks and responsibilities for casualties of every description in connection with the work, except that he shall not be held liable or responsible for delays or damage to the work caused by acts of God, acts of Public enemy, acts of Government, quarantine restrictions, general strikes through the trade, or by freight embargoes not caused or participated in by the Contractor. The Contractor shall have charge and control of the entire work until completion and acceptance of the same by the City.
- C. The Contractor shall alone be liable and responsible for, and shall pay, any and all loss or damage sustained by any person or party either during the performance or subsequent to the completion of the work under this agreement by reason of injuries to persons and damage to property, buildings, and adjacent work, that may occur either during the performance of the work covered by this contract or that may be sustained as a result of or in consequence thereof, irrespective of whether or not such injury or damage be due to negligence or the inherent nature of the work. Contractor will be responsible to reimburse the City for cost incurred for damages caused by the contractor's negligence or non-compliance with contract requirements.
- D. The Contractor shall bear all losses resulting from the amount or character of the work being different, or because the nature of the premises on which the work is done is different from what was expected, or on account of the weather, or similar other causes.

3.13 Insurance

The Contractor shall not commence work under this contract until he has obtained all the insurance required hereunder and such insurance has been approved by the City; nor shall the Contractor allow any Subcontractor to commence work on his subcontract until all similar insurance has been so obtained and approved. Approval

of the insurance by the City shall not relieve or decrease the liability of the Contractor hereunder.

- A. Worker's Compensation including Occupational Disease and Employer's Liability Insurance: The Contractor shall take out and maintain during the life of this Contract Workers' Compensation and Employer's Liability Insurance for all of his employees to be engaged in work on the project under this contract in an amount no less than the minimum allowed by the State Corporation Commission, and in case of such work is sublet, the Contractor shall require the Subcontractor similarly to provide Workers' Compensation and Employer's Liability Insurance for all of the latter's employees to be engaged in such work.
- B. Comprehensive General Liability Insurance: The Contractor shall maintain during the life of this Contract comprehensive general liability insurance as shall protect him, the City of Danville and its offices, agents and employees, and any Subcontractors performing work covered by this Contract from claims for damage for personal injury, including death, as well as from claims for property damage, which may arise from operations under this Contract, whether such operations by himself or by any Subcontractor, or by anyone directly or indirectly employed by either of them. The amount of such insurance shall not be less than a combination single limit of \$1,000,000 per occurrence on bodily injury and property damage and \$1,000,000 aggregate on completed operations. The comprehensive general liability insurance shall provide the following coverage:
- Comprehensive
 - Premises – Operation
 - Products/Completed Operations Hazard
 - Contractual Insurance
 - Underground Hazard
 - Explosion & Collapse Hazard
 - Independent Contractor and Subcontractor
 - Broad Form Property Damage
 - Personal Injury
 - Builders Risk
- C. Automobile liability insurance minimum combined single limits of \$1,000,000 for any one person and subject to the same limit for each person, \$1,000,000 on account of any one accident. This insurance shall include bodily injury and property damage for the following vehicles:
- Owned Vehicles
 - Non-owned Vehicles
 - Hired Vehicles
- D. Umbrella Policy. At the option of the Contractor, primary limits may be less than required, with an umbrella policy providing the additional limits needed. This form of insurance will be acceptable provided that the primary and umbrella policies both provide the insurance coverage's herein required. However, any such umbrella policy must have minimum coverage limits of \$3,000,000.00.
- E. All policies shall name the City of Danville, its officers, agents, and employees, as additional insured. This coverage shall be reflected on the Certificates of Insurance (including any endorsements or riders thereto), which will be provided

to the City. Each Certificate of Insurance shall require that notice be given thirty (30) days prior to cancellation or material change in the policies to the Director of Purchasing.

- F. Written evidence of the insurance required herein shall be filed with the City not later than thirty (30) days following the date of the award of the Contract. A copy of the evidence of insurance shall be filed with the Director of Purchasing.

3.14 Interpretation

- A. If any person contemplating the submission of a bid on this invitation is in doubt as to the true meaning of any part of the Invitation for bid or other documents, he should submit a written request for an interpretation thereof to the Engineer and received at least four (4) days before bid deadline. An interpretation of the bid invitation document will be made only by written addendum issued to each potential bidder. THE CITY WILL NOT BE RESPONSIBLE FOR EXPLANATIONS OR INTERPRETATIONS OF BID INVITATION DOCUMENTS EXCEPT AS ISSUED IN ACCORDANCE HEREWITH. The Bidder shall acknowledge receipt of all addenda in the Proposal.
- B. All notices, demands, requests, instructions, approvals, proposals, and claims must be in writing.
- C. If during performance of the Work, the Contractor finds a conflict, error or discrepancy in the Contract Documents, the contractor shall so report to the Engineer in writing at once before proceeding with the work affected thereby and shall obtain a written interpretation or clarification from the Engineer. In resolving such conflicts, errors and discrepancies, the Documents shall be given precedence in the following order: Agreement, Modifications, Addenda, Supplementary Conditions, Instruction to Bidders, General Conditions, Proposal and Specifications/Drawings. Figure dimensions on Drawings shall govern over scale dimensions and detailed drawings shall govern over general drawings.

3.15 Limitations of Work Area

- A. The Contractor shall be limited to a specific area for storage of equipment, supplies, and building materials. This area shall be designated by the City and established during the Pre-construction conference.
- B. Parking area for employees of the Contractor shall be designated in the vicinity of the project, and it shall be the responsibility of the Contractor to require his personnel to park in this designated area and not any area which may interfere with the normal operations in and around the construction area or with access and use of the facility by the City.

3.16 Novation

The Contractor shall not assign or transfer, whether by an Assignment or Novation, any of its rights, duties, benefits, obligations, liabilities or responsibilities under this Contract without the written consent of the City; provided, however, that assignments to banks, trust companies or other financial

institutions for the purpose of securing bond may be made without the consent of the City. Assignment or Novation of this Contract shall not be valid unless the Assignment or Novation expressly provides that the assignment of any of the Contractor's rights or benefits under the Contract is subject to a prior lien for labor performed, services rendered and materials, tools and equipment supplied for the performance of the work under this Contract in favor of all persons, firms or corporations rendering such labor or services or supplying such materials, tools and equipment.

3.17 Observance of Laws

The Contractor at all times shall observe and comply with all Federal, State and City laws, bylaws, ordinances and regulations in any manner affecting the conduct of the work or applying to employees on the project, as well as all orders or decrees which have been promulgated or enacted, by any legal bodies or tribunals having authority or jurisdiction over the work materials, employees or contract. The contractor does not, and shall not during the performance of the contract for goods and services in the Commonwealth; knowingly employ an unauthorized alien as defined in the federal Immigration Reform and Control Act of 1986.

3.18 Patents

The Contractor agrees to indemnify and save harmless the City, and all personnel from all suits and actions of every nature and description brought against them or any of the, for or on account of the use of patented appliances, products, or processes, and he shall pay all royalties and charges which are legal and equitable. Evidence of such payment or satisfaction shall be submitted upon request of the City as a necessary requirement in connection with the final execution of any contract in which such patented appliances, products, or processes are used.

3.19 Performance

In case of default by the Contractor, the City may procure the commodity or services from other sources and hold the Contractor responsible for any excess costs occasioned thereby.

3.20 Permits

The Contractor shall, at his own expense, secure any business or professional licenses, permits or fees required by the City of Danville, Commonwealth of Virginia or any other requesting agency having jurisdiction.

3.21 Safety

- A. All practices, materials and equipment shall comply with the Federal Occupational Safety and health Act, as well as any pertinent Federal, State and/or local Safety or Environmental Codes.
- B. Construction site safety is the responsibility of the Contractor.

3.22 Specifications and Product Description

When brand names, model numbers, trade names, catalog number or cuts are listed, they are, unless otherwise specified, included for the purpose of furnishing bidders with information concerning the style, type or kind of article desired and a bidder may offer an article which he certifies to be equal in quality, performance and other essential characteristics. Any available printed material or literature which describes the product being offered for sale shall be included with the bid. The City shall be the sole judge of suitability of substitutes offered. When a formal numbered specification is referred to in this invitation, no deviation will be permitted and the bidder will be required to furnish articles in conformity with that specification.

3.23 Subcontracts

- A. No proposed subcontractor shall be disapproved by the City except for cause.
- B. The Contractor shall be as fully responsible to the City for the acts and omissions of his subcontractors, and of persons either directly or indirectly employed by them as he is for the acts and omissions of persons directly employed by him.
- C. The Contractor shall cause appropriate provisions to be inserted in all subcontracts relative to the work to require compliance by each subcontractor with the applicable provisions of the Contract for the improvements embraced in this Contract.
- D. Nothing contained in the Contract shall create any contractual relation between any subcontractor and the City.
- E. Payments to subcontractors
 - 1. The contractor shall take one of the two following actions within seven days after receipt of amounts paid to the contractor by the City of Danville for work performed by the subcontractor;
 - a. Pay the subcontractor for the proportionate share of the total payment received from the agency attributable to the work performed by the subcontractor under that contract; or
 - b. Notify the agency and subcontractor, in writing, of his intention to withhold all or a part of the subcontractor's payment with the reason for nonpayment.
 - 2. Individual Contractors shall provide their social security numbers and proprietorships, partnerships, and corporations to provide their federal employer identification numbers.
 - 3. The contractor shall pay interest to the subcontractor on all amounts owed by the contractor that remain unpaid after seven days following receipt by the contractor of payment from the City of Danville for work

performed by the subcontractor, except for amounts withheld as allowed in subdivision 1.

4. Unless otherwise provided under the terms of this contract, interest shall accrue at the rate of one percent per month.” The contractor shall include in each of its subcontracts a provision requiring each subcontractor to include or otherwise be subject to the same payment and interest requirements with respect to each lower-tier subcontractor.

A contractor's obligation to pay an interest charge to a subcontractor pursuant to the payment clause in this section shall not be construed to be an obligation of the City of Danville. A contract modification shall not be made for the purpose of providing reimbursement for the interest charge. A cost reimbursement claim shall not include any amount for reimbursement for the interest charge.

3.24 Suspension of Work

The work may be suspended by the City when deemed in the best interest of the City.

3.25 Termination

If the Contractor fails to begin the work under this contract within the time specified, or fails to perform the work with sufficient workmen and equipment or with sufficient materials to insure the completion of said work within the specified time, or shall perform the work in an unsatisfactory manner, or shall neglect or refuse to remove materials or perform anew such work as shall discontinue the prosecution of the work, or if the Contractor shall become insolvent or be declared bankrupt, or shall commit any act of bankruptcy or insolvency, or shall make an assignment for the benefit of creditors, or from any other cause whatsoever shall not carry out the work in an acceptable manner, the City shall give notice in writing to the Contractor and his surety of such failure, delay, neglect, refusal, or default, specifying the same and if the contractor, within a period of seven days after such notice, shall not proceed in accordance therewith, then the City Manager acting for and on behalf of the City shall, upon receipt of a written certificate from the Engineer of the fact of such failure, delay, neglect, refusal, or default and of failure of the Contractor to comply with such notice, have full power and authority to declare the forfeiture of this contract, and to forfeit the rights of the Contractor in this contract, and the City Manager at this option may call upon the surety to complete the work in accordance with the terms of this contract or may have the City take over the terms of this contract or may have the City take over the work, including any or all materials and equipment on the ground as may be suitable and acceptable to the City and may complete the work by or on its own employees, or may enter into a new contract for the completion of the work, or may use such other methods as in the opinion of the City Manager shall be required for the completion of the work in an acceptable manner. All costs and charges incurred by the City, together with the cost of completing the work, shall be deducted from any monies due or which may become due on this contract.

In case the expense so incurred by the City shall be less than the sum which would have been payable under this contract if it had been completed by the

Contractor and had not been forfeited by the City, then the Contractor shall be entitled to receive the difference, subject to any claims of liens thereon which may have been filed with the City or any prior assignment filed with it. In case such expense shall exceed the sum which would have been payable under this contract, the Contractor and the surety shall be liable and shall pay the City the amount of such excess.

3.26 Work Changes

- A. The City without invalidating the contract, and without notice to any surety, may order changes in the work within the general scope of the contract consisting of additions, deletions or other revisions, providing the total amount added or eliminated does not exceed twenty-five percent (25%) of the total contract price, or \$50,000, whichever is greater. All such changes in the work shall be authorized by change order, and shall be executed under the applicable conditions of the contract documents.
- B. The cost or credit to the City resulting from a change in the work shall be determined by unit prices subsequently agreed upon or by mutual acceptance of a lump sum properly itemized, or on the basis of cost of Work plus a Contractors Fee for overhead and profit as determined below.
- C. Should concealed conditions encountered in the performance of the work below the surface of the ground or hidden in existing structures be at variance with the conditions indicated by the contract documents, the contract price may be equitably adjusted by change order upon claim by either party and approval of the other party, made within either party and approval of the other party, made within twenty (20) days after the first observance of the conditions.
- D. The Contractor shall promptly, and before such conditions are disturbed, notify the Project Manager in writing of: (a) subsurface or latent physical conditions at the site differing materially from those indicated in this contract, or (b) unknown physical conditions at the site, of an unusual nature, differing materially from those ordinarily encountered and generally recognized as inherent in work of the character provided for in this contract. The Project Manager shall promptly investigate the conditions, and if he finds that such conditions do so materially differ and cause an increase or decrease in the contractor's cost of, or the time required for, performance of this contract, and equitable adjustment shall be made and the contract modified in writing accordingly. Any claim of the Contractor for adjustment hereunder shall not be allowed unless he has given notice as above required; or unless the Project Manager grants a further period of time before the date of final payment under the contract.

City of Danville

IFB 18-19-014

Bid Proposal

"City Auditorium Roof Replacement Project"

The undersigned, as Bidder, hereby declares that he or he and his associates are the only person or persons interested in the proposal as principal or principals; that this proposal is made without connection with any other person, company or parties making a bid or proposal; and that it is in all respects fair and in good faith without collusion or fraud.

The Bidder further declares that he has examined the site of the work and informed himself fully in regard to all conditions pertaining to the place where the work is to be done; that he has examined specifications for the work and contractual documents relative thereto, and has read all special provisions furnished prior to the bid opening; that he has satisfied himself relative to the work to be performed, and materials and equipment to be furnished.

The Bidder proposes and agrees, if this proposal is accepted, to contract with the City of Danville, Virginia in the form of contract specified, to furnish all necessary materials, equipment, machines, tools apparatus, means of transportation, and labor necessary to perform in full and complete the requirements of the specifications and contract documents, to the full and entire satisfaction of the City of Danville, Virginia with definite understanding that no money will be allowed for extra work except as set forth in the attached General Conditions and Contract Documents, as follows:

A. Base Bid

Lump Sum Bid for the replacement of the roof at the City Auditorium as described in the Contract Documents:

\$ _____ (\$ _____)

Included in the Base Bid is a lump sum for metal deck repair and replacement. See Specification Section 012200 for a complete description. The contractor shall provide the unit prices and extended total that is included in the Base Bid.

Repair: Estimated Quantity: 225 SF @ \$ _____ per SF = \$ _____.

Replacement: Estimated Quantity: 600 SF @ \$ _____ per SF = \$ _____.

If actual quantities increase or decrease, the contract sum will be adjusted accordingly based on the unit price provided above.

Bidders must provide bids for Base Bid and Unit Prices. Failure to do so may be grounds for rejection of the entire bid.

My signature certifies that the accompanying bid is not the result of or affected by any act of collusion with another person or company engaged in the same line of business or commerce, or any act of fraud punishable under Title 18.2, Chapter 12, Article 1.1 of the Code of Virginia, 1950, as amended. Furthermore, I understand that fraudulent and collusive bidding is a crime under the Virginia Governmental Frauds Act, the Virginia Government Bid Rigging Act, and

Virginia Antitrust Act, and Federal Law and can result in fines, prison sentences, and civil damage awards. I hereby certify that I am authorized to sign this bid for the BIDDER.

The Bidder further agrees that:

1. The City, in protecting its best interest, reserves the right to reject any or all bids or waive any defects in favor of the City. Any changes, erasures, deletions in the unit or lump sum prices above, modifications in the bid form, or alternate proposals not specified in the bid proposal shall make the proposal irregular and subject to rejection.

2. All quantities listed above are estimates only and the City reserves the right to raise, lower, or eliminate any quantity or item and in any case the unit or lump sum prices shall be used in determining partial or final payment.

3. If awarded the contract, to execute and deliver to the City within ten (10) consecutive calendar days after their receipt of the contract documents, a satisfactory Performance Bond and Labor & Material Bond, as required, in the amount of one hundred percent (100%) of the contract amount along with the signed agreement.

4. In case of failure on their part to execute the said agreement within ten (10) consecutive calendar days after receipt of the contract documents, the monies payable by the Security accompanying this bid shall be paid to the City of Danville, Virginia, as liquidated damages for such failure; otherwise, the Security accompanying this bid shall be returned to the Bidder.

5. The work under this contract shall commence not later than five (5) consecutive calendar days after the date of a written Notice To Proceed is given by the City to the Contractor and shall be completed in ninety (90) calendar days.

6. The amount of Liquidated Damage, as stipulated in the specifications, shall be three hundred (\$300.00) for each day, including Saturdays, Sundays, and Holidays, after the established date of completion.

7. This bid is subject to acceptance within a period of ninety (90) days from the date of this bid.

Enclosed herewith is the following Security, offered as evidence that the undersigned will enter into agreement for the execution and completion of the work in accordance with the drawings and specifications.

Bidder's Bond or Certified Check in the amount of \$ _____

If Bond, Name of Surety: _____

If Check, Name of Bank: _____

If awarded this contract, since our bid is \$200,000 or more, I/We elect to utilize the escrow account procedure in the Standard Requirements & Instructions for Bidding.

(Write Yes or No)

The undersigned Bidder acknowledges receipt of the following Addenda, which have been considered in the preparation of this Bid:

No. _____ Dated _____

No. _____ Dated _____

Company Name _____ Date _____

Address _____

Signature _____ Zip Code _____

Affix Company Seal
(if applicable)

Signature (Printed) _____

Title _____

Phone _____ Fax _____

Commonwealth of VA Contractor License # _____

City of Danville business license # _____

Commonwealth of VA State Corporation Identification # _____

SECTION 011000 - SUMMARY

PART 1 - GENERAL

1.1 SUMMARY

A. Section includes:

1. Project information.
2. Work covered by Contract Documents.
3. Work under separate contracts.
4. Access to site.
5. Work restrictions.
6. Specification and drawing conventions.

B. Related Section:

1. Division 01 Section "Temporary Facilities and Controls" for limitations and procedures governing temporary use of Owner's facilities.

1.2 PROJECT INFORMATION

A. Project Identification:

1. City of Danville – City Auditorium
 - a. Project Location: 125 North Floyd Street, Danville, VA 24541.

B. Owner: City of Danville.

1. Owner's Representative: Walter Lucas, Public Works, (434) 799-5245

C. Architect: Dewberry Engineers Inc., 551 Piney Forest Road, Danville, VA 24540.

1.3 WORK COVERED BY CONTRACT DOCUMENTS

A. The Work of the Project is defined by the Contract Documents and consists of the following:

1. City Auditorium Roof Replacement Project
 - a. Replace existing roof system with a 60 MIL fully adhered EPDM membrane roof system.

B. Type of Contract.

1. Project will be constructed under a single prime contract.

1.4 WORK UNDER SEPARATE CONTRACTS

- A. General: Cooperate fully with separate contractors so work on those contracts may be carried out smoothly, without interfering with or delaying work under this Contract or other contracts. Coordinate the Work of this Contract with work performed under separate contracts.

1.5 ACCESS TO SITE

- A. General: Contractor shall have limited use of Project site for construction operations as indicated on Drawings by the Contract limits and as indicated by requirements of this Section.
- B. Use of Site: Limit use of Project site to work in areas indicated. Do not disturb portions of Project site beyond areas in which the Work is indicated.
 - 1. Driveways, Walkways and Entrances: Keep driveways, loading areas, and entrances serving premises clear and available to Owner, Owner's employees, and emergency vehicles at all times. Do not use these areas for parking or storage of materials.
 - a. Schedule deliveries to minimize use of driveways and entrances by construction operations.
 - b. Schedule deliveries to minimize space and time requirements for storage of materials and equipment on-site.
- C. Condition of Existing Building: Maintain portions of existing building affected by construction operations in a weathertight condition throughout construction period. Repair damage caused by construction operations.

1.6 COORDINATION WITH OCCUPANTS

- A. Owner Occupancy: Owner will occupy the premises during entire construction period, with the exception of areas under construction. Cooperate with Owner during construction operations to minimize conflicts and facilitate Owner usage. Perform the Work so as not to interfere with Owner's operations. Maintain existing exits unless otherwise indicated.
 - 1. Maintain access to existing walkways, corridors, and other adjacent occupied or used facilities. Do not close or obstruct walkways, corridors, or other occupied or used facilities without written permission from Owner and authorities having jurisdiction.
 - 2. Provide not less than 72 hours' notice to Owner of activities that will affect Owner's operations.

1.7 WORK RESTRICTIONS

- A. Work Restrictions, General: Comply with restrictions on construction operations.
 - 1. Comply with limitations on use of public streets and with other requirements of authorities having jurisdiction.
- B. On-Site Work Hours: Limit work in the existing building to normal business working hours of 7:00 a.m. to 5:00 p.m., Monday through Friday, unless otherwise indicated.

1. Weekend Hours: Contractor may work on weekends subject to prior approval of the Owner.
 2. Extended Hours: Contractor may work extended hours subject to prior approval of the Owner.
- C. Existing Utility Interruptions: Do not interrupt utilities serving facilities occupied by Owner or others unless permitted under the following conditions and then only after providing temporary utility services according to requirements indicated:
1. Notify Owner not less than two days in advance of proposed utility interruptions.
- D. Noise, Vibration, and Odors: Coordinate operations that may result in high levels of noise and vibration, odors, or other disruption to Owner occupancy with Owner.
1. Notify Owner not less than two days in advance of proposed disruptive operations.
- E. Nonsmoking Building: Smoking is not permitted within the building or within 25 feet of entrances, operable windows, or outdoor-air intakes.
- F. Controlled Substances: Use of tobacco products and other controlled substances within the existing building is not permitted.
- G. Employee Identification: Provide identification tags for Contractor personnel working on Project site. Require personnel to use identification tags at all times.
- H. Per contract documents the general contractor shall access the roof from inside the building for personnel and from outside the building for material.
1. Should any of the general contractor employees or subcontractor employees working on this project enter the building for any reason the general contractor shall provide the following prior to workers entering the building:

Written certification that all employees and all subcontractors employees have not been convicted of a felony in the past 7 years, can qualify for voting rights reinstatement and are not on active parole or active probation. Workers with felony convictions and do not qualify under special conditions will not be allowed access to the building.
- I. The City of Danville will not waive landfill fees for tear-off debris.

1.8 SPECIFICATION AND DRAWING CONVENTIONS

- A. Specification Content: The Specifications use certain conventions for the style of language and the intended meaning of certain terms, words, and phrases when used in particular situations. These conventions are as follows:
1. Imperative mood and streamlined language are generally used in the Specifications. The words "shall," "shall be," or "shall comply with," depending on the context, are implied where a colon (:) is used within a sentence or phrase.
 2. Specification requirements are to be performed by Contractor unless specifically stated otherwise.

- B. Division 01 General Requirements: Requirements of Sections in Division 01 apply to the Work of all Sections in the Specifications.
- C. Drawing Coordination: Requirements for materials and products identified on the Drawings are described in detail in the Specifications. One or more of the following are used on the Drawings to identify materials and products:
 - 1. Terminology: Materials and products are identified by the typical generic terms used in the individual Specifications Sections.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 011000

SECTION 012200 - UNIT PRICES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for unit prices.

1.2 DEFINITIONS

- A. Unit price is an amount proposed by bidders, stated on Bid Form as a price per unit of measurement for materials, equipment, or services, or a portion of the Work, added to or deducted from the Contract Sum by appropriate modification, if the scope of Work or estimated quantities of Work required by the Contract Documents are increased or decreased.

1.3 PROCEDURES

- A. Unit prices include all necessary material, plus cost for delivery, installation, insurance, applicable taxes, overhead, and profit.
- B. Measurement and Payment: See individual Specification Sections for work that requires establishment of unit prices. Methods of measurement and payment for unit prices are specified in those Sections.
- C. Owner reserves the right to reject Contractor's measurement of work-in-place that involves use of established unit prices and to have this work measured, at Owner's expense, by an independent surveyor acceptable to Contractor.
- D. List of Unit Prices: A schedule of unit prices is included in Part 3. Specification Sections referenced in the schedule contain requirements for materials described under each unit price.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 SCHEDULE OF UNIT PRICES

- A. Repair and Replacement of Deteriorated Metal Decking
 - 1. Repairs: At locations where roof damage is found to be less than 1'-0" by 1'-0" in size, repair may be made by placing a 3'-0" by 3'-0" by 18 gauge steel plate over the damaged area. Secure corners of steel plate to existing deck with #10 TEC screws. Steel plate shall be field primed and painted if exposed over the gym area.

2. Replacement: At locations where existing roof deck has been damaged significantly due to rust corrosion, remove and replace roof deck from centerline to centerline of existing steel beam supports (approximately 8'-0" o.c. field verify). Replacement roof deck shall be 1-1/2" deep, 18 gauge, 36" wide narrow rib roof deck, shall be factory primed painted white (Type 3 Finish) and if exposed over the gym area field painted to match existing deck (2 coats high performance architectural latex, semigloss) by Sherwin Williams. Replacement roof deck shall be connected to steel beam supports with 5/8" diameter puddle welds at each flute. Fasten side lap attachments of replacement roof deck at 3'-0" on center maximum spacing using #10 TEK screws. Provide metal deck by Vulcraft or equal.

END OF SECTION 012200

SECTION 012500 - SUBSTITUTION PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for substitutions.
- B. Related Section:
 - 1. Division 01 Section "Product Requirements" for requirements for submitting comparable product submittals for products by listed manufacturers.

1.2 DEFINITIONS

- A. Substitutions: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents and proposed by Contractor.

1.3 SUBMITTALS

- A. Substitution Requests: Submit three copies of each request for consideration. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
 - 1. Substitution Request Form: Use CSI Form 13.1A.
 - 2. Documentation: Show compliance with requirements for substitutions and the following, as applicable:
 - a. Statement indicating why specified product or fabrication or installation cannot be provided, if applicable.
 - b. Coordination information, including a list of changes or modifications needed to other parts of the Work and to construction performed by Owner and separate contractors, that will be necessary to accommodate proposed substitution.
 - c. Detailed comparison of significant qualities of proposed substitution with those of the Work specified. Include annotated copy of applicable specification section. Significant qualities may include attributes such as performance, weight, size, durability, visual effect, sustainable design characteristics, warranties, and specific features and requirements indicated. Indicate deviations, if any, from the Work specified.
 - d. Product Data, including drawings and descriptions of products and fabrication and installation procedures.
 - e. Samples, where applicable or requested.
 - f. Cost information, including a proposal of change, if any, in the Contract Sum.
 - g. Contractor's certification that proposed substitution complies with requirements in the Contract Documents except as indicated in substitution request, is compatible with related materials, and is appropriate for applications indicated.

- h. Contractor's waiver of rights to additional payment or time that may subsequently become necessary because of failure of proposed substitution to produce indicated results.
- 3. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within seven days of receipt of a request for substitution. Architect will notify Contractor of acceptance or rejection of proposed substitution within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.
 - a. Forms of Acceptance: Change Order, Construction Change Directive, or Architect's Supplemental Instructions for minor changes in the Work.
 - b. Use product specified if Architect does not issue a decision on use of a proposed substitution within time allocated.

1.4 QUALITY ASSURANCE

- A. Compatibility of Substitutions: Investigate and document compatibility of proposed substitution with related products and materials. Engage qualified testing agency to perform compatibility tests recommended by manufacturers.

PART 2 - PRODUCTS

2.1 SUBSTITUTIONS

- A. Substitutions for Cause: Submit requests for substitution immediately upon discovery of need for change, but not later than 15 days prior to time required for preparation and review of related submittals.
 - 1. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied:
 - a. Requested substitution is consistent with the Contract Documents and will produce indicated results.
 - b. Requested substitution will not adversely affect Contractor's construction schedule.
 - c. Requested substitution has received necessary approvals of authorities having jurisdiction.
 - d. Requested substitution is compatible with other portions of the Work.
 - e. Requested substitution has been coordinated with other portions of the Work.
 - f. Requested substitution provides specified warranty.
 - g. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.
- B. Substitutions for Convenience: Not allowed.
- C. Substitutions for roofing materials and roofing material manufacturers must be submitted ten (10) days prior to bid opening and any approved substitutions must be included in an addendum.

PART 3 - EXECUTION (Not Used)

END OF SECTION 012500

SECTION 012600 - CONTRACT MODIFICATION PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for handling and processing Contract modifications.

1.2 MINOR CHANGES IN THE WORK

- A. Architect will issue supplemental instructions authorizing minor changes in the Work, not involving adjustment to the Contract Sum or the Contract Time, on AIA Document G710, "Architect's Supplemental Instructions."

1.3 PROPOSAL REQUESTS

- A. Owner-Initiated Proposal Requests: Architect will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or the Contract Time. If necessary, the description will include supplemental or revised Drawings and Specifications.
 - 1. Proposal Requests issued by Architect are not instructions either to stop work in progress or to execute the proposed change.
 - 2. Within time specified in Proposal Request after receipt of Proposal Request, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time necessary to execute the change.
 - a. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
 - b. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
 - c. Include costs of labor and supervision directly attributable to the change.
 - d. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
- B. Contractor-Initiated Proposals: If latent or changed conditions require modifications to the Contract, Contractor may initiate a claim by submitting a request for a change to Architect.
 - 1. Include a statement outlining reasons for the change and the effect of the change on the Work. Provide a complete description of the proposed change. Indicate the effect of the proposed change on the Contract Sum and the Contract Time.
 - 2. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.

3. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
4. Include costs of labor and supervision directly attributable to the change.
5. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
6. Comply with requirements in Division 01 Section "Substitution Procedures" if the proposed change requires substitution of one product or system for product or system specified.

1.4 CHANGE ORDER PROCEDURES

- A. On Owner's approval of a Proposal Request, Architect will issue a Change Order for signatures of Owner and Contractor on AIA Document G701.

1.5 CONSTRUCTION CHANGE DIRECTIVE

- A. Construction Change Directive: Architect may issue a Construction Change Directive on AIA Document G714. Construction Change Directive instructs Contractor to proceed with a change in the Work, for subsequent inclusion in a Change Order.
 1. Construction Change Directive contains a complete description of change in the Work. It also designates method to be followed to determine change in the Contract Sum or the Contract Time.
- B. Documentation: Maintain detailed records on a time and material basis of work required by the Construction Change Directive.
 1. After completion of change, submit an itemized account and supporting data necessary to substantiate cost and time adjustments to the Contract.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012600

SECTION 012900 - PAYMENT PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

- A. This Section specifies administrative and procedural requirements necessary to prepare and process Applications for Payment.

1.2 SCHEDULE OF VALUES

- A. Coordination: Coordinate preparation of the schedule of values with preparation of Contractor's construction schedule.
 - 1. Correlate line items in the schedule of values with other required administrative forms and schedules, including the following:
 - a. Application for Payment forms with continuation sheets.
 - 2. Submit the schedule of values to Architect at earliest possible date but no later than seven days before the date scheduled for submittal of initial Applications for Payment.
- B. Format and Content: Use the Project Manual table of contents as a guide to establish line items for the schedule of values. Provide at least one line item for each Specification Section.
 - 1. Identification: Include the following Project identification on the schedule of values:
 - a. Project name and location.
 - b. Name of Architect.
 - c. Architect's project number.
 - d. Contractor's name and address.
 - e. Date of submittal.
 - 2. Arrange schedule of values consistent with format of AIA Document G703.
 - 3. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Coordinate with the Project Manual table of contents. Provide multiple line items for principal subcontract amounts in excess of five percent of Contract Sum.
 - 4. Round amounts to nearest whole dollar; total shall equal the Contract Sum.
 - 5. Provide a separate line item in the schedule of values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.
 - 6. Provide separate line items in the schedule of values for initial cost of materials, for each subsequent stage of completion, and for total installed value of that part of the Work.
 - 7. Each item in the schedule of values and Applications for Payment shall be complete. Include total cost and proportionate share of general overhead and profit for each item.

- a. Temporary facilities and other major cost items that are not direct cost of actual work-in-place may be shown either as separate line items in the schedule of values or distributed as general overhead expense, at Contractor's option.

1.3 APPLICATIONS FOR PAYMENT

- A. Each Application for Payment shall be consistent with previous applications and payments as certified by Architect and paid for by Owner.
 1. Initial Application for Payment, Application for Payment at time of Substantial Completion, and final Application for Payment involve additional requirements.
- B. Payment Application Times: The date for each progress payment is indicated in the Agreement between Owner and Contractor. The period of construction work covered by each Application for Payment is the period indicated in the Agreement.
- C. Application for Payment Forms: Use AIA Document G702 and AIA Document G703 as form for Applications for Payment.
- D. Application Preparation: Complete every entry on form. Notarize and execute by a person authorized to sign legal documents on behalf of Contractor. Architect will return incomplete applications without action.
 1. Entries shall match data on the schedule of values and Contractor's construction schedule. Use updated schedules if revisions were made.
 2. Include amounts of Change Orders and Construction Change Directives issued before last day of construction period covered by application.
- E. Transmittal: Submit three signed and notarized original copies of each Application for Payment to Architect by a method ensuring receipt within 24 hours.
 1. Transmit each copy with a transmittal form listing attachments and recording appropriate information about application.
- F. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:
 1. List of subcontractors.
 2. Schedule of values.
 3. Contractor's construction schedule (preliminary if not final).
 4. Copies of building permits.
 5. Copies of authorizations and licenses from authorities having jurisdiction for performance of the Work.
 6. Initial progress report.
 7. Certificates of insurance and insurance policies.
- G. Application for Payment at Substantial Completion: After issuing the Certificate of Substantial Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.

- H. Final Payment Application: Submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:
1. Evidence of completion of Project closeout requirements.
 2. AIA Document G706-1994, "Contractor's Affidavit of Payment of Debts and Claims."
 3. AIA Document G706A-1994, "Contractor's Affidavit of Release of Liens."
 4. AIA Document G707-1994, "Consent of Surety to Final Payment."
- I. Application for Payment: Submit invoices for each pay request if requesting payment for materials properly stored on site. The Owner will allow a 5% markup on invoices of materials properly stored on site. The Owner holds a 5% retainage on all properly stored materials.
- J. Retainage: A 5% retainage will be withheld from each pay request until the project is 100% completed.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012900

SECTION 013100 - PROJECT MANAGEMENT AND COORDINATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes administrative provisions for coordinating construction operations on Project including, but not limited to, the following:
 - 1. General project coordination procedures.
 - 2. Coordination drawings.
 - 3. Requests for Information (RFIs).
 - 4. Project meetings.
- B. Related Sections:
 - 1. Division 01 Section "Construction Progress Documentation" for preparing and submitting Contractor's construction schedule.
 - 2. Division 01 Section "Execution" for procedures for coordinating general installation and field-engineering services, including establishment of benchmarks and control points.
 - 3. Division 01 Section "Closeout Procedures" for coordinating closeout of the Contract.

1.3 DEFINITIONS

- A. RFI: Request from Owner, Architect, or Contractor seeking information from each other during construction.

1.4 COORDINATION

- A. Coordination: Coordinate construction operations included in different Sections of the Specifications to ensure efficient and orderly installation of each part of the Work. Coordinate construction operations, included in different Sections, that depend on each other for proper installation, connection, and operation.
 - 1. Schedule construction operations in sequence required to obtain the best results where installation of one part of the Work depends on installation of other components, before or after its own installation.
 - 2. Coordinate installation of different components to ensure maximum performance and accessibility for required maintenance, service, and repair.
 - 3. Make adequate provisions to accommodate items scheduled for later installation.

- B. Administrative Procedures: Coordinate scheduling and timing of required administrative procedures with other construction activities to avoid conflicts and to ensure orderly progress of the Work. Such administrative activities include, but are not limited to, the following:
1. Preparation of Contractor's construction schedule.
 2. Preparation of the schedule of values.
 3. Installation and removal of temporary facilities and controls.
 4. Delivery and processing of submittals.
 5. Progress meetings.
 6. Preinstallation conferences.
 7. Project closeout activities.

1.5 COORDINATION DRAWINGS

- A. Coordination Drawings, General: Prepare coordination drawings in accordance with requirements in individual Sections, where installation is not completely shown on Shop Drawings, where limited space availability necessitates coordination, or if coordination is required to facilitate integration of products and materials fabricated or installed by more than one entity.
1. Content: Project-specific information, drawn accurately to a scale large enough to indicate and resolve conflicts. Do not base coordination drawings on standard printed data. Include the following information, as applicable:
 - a. Use applicable Drawings as a basis for preparation of coordination drawings. Prepare sections, elevations, and details as needed to describe relationship of various systems and components.
 - b. Coordinate the addition of trade-specific information to the coordination drawings by multiple contractors in a sequence that best provides for coordination of the information and resolution of conflicts between installed components before submitting for review.
 - c. Indicate functional and spatial relationships of components of architectural, structural, civil, mechanical, and electrical systems.
 - d. Indicate space requirements for routine maintenance and for anticipated replacement of components during the life of the installation.
 - e. Show location and size of access doors required for access to concealed dampers, valves, and other controls.
 - f. Indicate required installation sequences.
 - g. Indicate dimensions shown on the Drawings. Specifically note dimensions that appear to be in conflict with submitted equipment and minimum clearance requirements. Provide alternate sketches to Architect indicating proposed resolution of such conflicts. Minor dimension changes and difficult installations will not be considered changes to the Contract.

1.6 REQUESTS FOR INFORMATION (RFIs)

- A. General: Immediately on discovery of the need for additional information or interpretation of the Contract Documents, Contractor shall prepare and submit an RFI in the form specified.

1. Architect will return RFIs submitted to Architect by other entities controlled by Contractor with no response.
 2. Coordinate and submit RFIs in a prompt manner so as to avoid delays in Contractor's work or work of subcontractors.
- B. Content of the RFI: Include a detailed, legible description of item needing information or interpretation and the following:
1. Project name.
 2. Project number.
 3. Date.
 4. Name of Contractor.
 5. Name of Architect.
 6. RFI number, numbered sequentially.
 7. RFI subject.
 8. Specification Section number and title and related paragraphs, as appropriate.
 9. Drawing number and detail references, as appropriate.
 10. Field dimensions and conditions, as appropriate.
 11. Contractor's suggested resolution. If Contractor's solution(s) impacts the Contract Time or the Contract Sum, Contractor shall state impact in the RFI.
 12. Contractor's signature.
 13. Attachments: Include sketches, descriptions, measurements, photos, Product Data, Shop Drawings, coordination drawings, and other information necessary to fully describe items needing interpretation.
 - a. Include dimensions, thicknesses, structural grid references, and details of affected materials, assemblies, and attachments on attached sketches.
- C. RFI Forms: AIA Document G716.
- D. Architect's Action: Architect will review each RFI, determine action required, and respond. Allow seven working days for Architect's response for each RFI. RFIs received by Architect after 1:00 p.m. will be considered as received the following working day.
1. The following RFIs will be returned without action:
 - a. Requests for approval of submittals.
 - b. Requests for approval of substitutions.
 - c. Requests for coordination information already indicated in the Contract Documents.
 - d. Requests for adjustments in the Contract Time or the Contract Sum.
 - e. Requests for interpretation of Architect's actions on submittals.
 - f. Incomplete RFIs or inaccurately prepared RFIs.
 2. Architect's action may include a request for additional information, in which case Architect's time for response will date from time of receipt of additional information.
 3. Architect's action on RFIs that may result in a change to the Contract Time or the Contract Sum may be eligible for Contractor to submit Change Proposal according to Division 01 Section "Contract Modification Procedures."

- a. If Contractor believes the RFI response warrants change in the Contract Time or the Contract Sum, notify Architect in writing within 10 days of receipt of the RFI response.
- E. On receipt of Architect's action, update the RFI log and immediately distribute the RFI response to affected parties. Review response and notify Architect within seven days if Contractor disagrees with response.
- F. RFI Log: Prepare, maintain, and submit a tabular log of RFIs organized by the RFI number. Submit log biweekly. Include the following:
 - 1. Project name.
 - 2. Name and address of Contractor.
 - 3. Name and address of Architect.
 - 4. RFI number including RFIs that were dropped and not submitted.
 - 5. RFI description.
 - 6. Date the RFI was submitted.
 - 7. Date Architect's response was received.
 - 8. Identification of related Minor Change in the Work, Construction Change Directive, and Proposal Request, as appropriate.
 - 9. Identification of related Field Order, Work Change Directive, and Proposal Request, as appropriate.

1.7 PROJECT MEETINGS

- A. General: Schedule and conduct meetings and conferences at Project site, unless otherwise indicated.
 - 1. Attendees: Inform participants and others involved, and individuals whose presence is required, of date and time of each meeting. Notify Owner and Architect of scheduled meeting dates and times.
 - 2. Agenda: Prepare the meeting agenda. Distribute the agenda to all invited attendees.
 - 3. Minutes: Entity responsible for conducting meeting will record significant discussions and agreements achieved. Distribute the meeting minutes to everyone concerned, including Owner and Architect, within three days of the meeting.
- B. Preconstruction Conference: Architect will schedule and conduct a preconstruction conference before starting construction, at a time convenient to Owner and Architect, but no later than 15 days after execution of the Agreement.
 - 1. Conduct the conference to review responsibilities and personnel assignments.
 - 2. Attendees: Authorized representatives of Owner, Architect, and their consultants; Contractor and its superintendent; major subcontractors; suppliers; and other concerned parties shall attend the conference. Participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work.
 - 3. Agenda: Discuss items of significance that could affect progress, including the following:
 - a. Tentative construction schedule.
 - b. Critical work sequencing and long-lead items.

- c. Designation of key personnel and their duties.
 - d. Lines of communications.
 - e. Procedures for processing field decisions and Change Orders.
 - f. Procedures for RFIs.
 - g. Procedures for testing and inspecting.
 - h. Procedures for processing Applications for Payment.
 - i. Submittal procedures.
 - j. Preparation of record documents.
 - k. Use of the premises and existing building.
 - l. Work restrictions.
 - m. Working hours.
 - n. Owner's occupancy requirements.
 - o. Responsibility for temporary facilities and controls.
 - p. Procedures for disruptions and shutdowns.
 - q. Parking availability.
 - r. Office, work, and storage areas.
 - s. Equipment deliveries and priorities.
 - t. Security.
 - u. Progress cleaning.
4. Minutes: Entity responsible for conducting meeting will record and distribute meeting minutes.

C. Progress Meetings: General Contractor shall conduct progress meetings at biweekly intervals.

- 1. Coordinate dates of meetings with preparation of payment requests.
- 2. Attendees: In addition to representatives of Owner and Architect, each contractor, subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the meeting shall be familiar with Project and authorized to conclude matters relating to the Work.
- 3. Agenda: Review and correct or approve minutes of previous progress meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.
 - a. Contractor's Construction Schedule: Review progress since the last meeting. Determine whether each activity is on time, ahead of schedule, or behind schedule, in relation to Contractor's construction schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.
 - 1) Review schedule for next period.
 - b. Review present and future needs of each entity present, including the following:
 - 1) Interface requirements.
 - 2) Sequence of operations.
 - 3) Status of submittals.
 - 4) Deliveries.
 - 5) Off-site fabrication.

- 6) Access.
 - 7) Site utilization.
 - 8) Temporary facilities and controls.
 - 9) Progress cleaning.
 - 10) Quality and work standards.
 - 11) Status of correction of deficient items.
 - 12) Field observations.
 - 13) Status of RFIs.
 - 14) Status of proposal requests.
 - 15) Pending changes.
 - 16) Status of Change Orders.
 - 17) Pending claims and disputes.
 - 18) Documentation of information for payment requests.
4. Minutes: Entity responsible for conducting the meeting will record and distribute the meeting minutes to each party present and to parties requiring information.
- a. Schedule Updating: Revise Contractor's construction schedule after each progress meeting where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with the report of each meeting.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 013100

SECTION 013200 - CONSTRUCTION PROGRESS DOCUMENTATION

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for documenting the progress of construction during performance of the Work, including the following:
 - 1. Contractor's construction schedule.
 - 2. Field condition reports.

1.2 INFORMATIONAL SUBMITTALS

- A. Contractor's Construction Schedule: Initial schedule, of size required to display entire schedule for entire construction period.
- B. Field Condition Reports: Submit at time of discovery of differing conditions.

1.3 COORDINATION

- A. Coordinate preparation and processing of schedules and reports with performance of construction activities and with scheduling and reporting of separate contractors.
- B. Coordinate Contractor's construction schedule with the schedule of values, payment requests, and other required schedules and reports.
 - 1. Secure time commitments for performing critical elements of the Work from entities involved.
 - 2. Coordinate each construction activity in the network with other activities and schedule them in proper sequence.

PART 2 - PRODUCTS

2.1 CONTRACTOR'S CONSTRUCTION SCHEDULE, GENERAL

- A. Time Frame: Extend schedule from date established for the Notice to Proceed to date of final completion.
 - 1. Contract completion date shall not be changed by submission of a schedule that shows an early completion date, unless specifically authorized by Change Order.
- B. Constraints: Include constraints and work restrictions indicated in the Contract Documents and as follows in schedule, and show how the sequence of the Work is affected.

1. Phasing: Arrange list of activities on schedule by phase.
2. Work Restrictions: Show the effect of the following items on the schedule:
 - a. Coordination with existing construction.
 - b. Limitations of continued occupancies.
 - c. Uninterruptible services.
 - d. Partial occupancy before Substantial Completion.
 - e. Use of premises restrictions.

2.2 CONTRACTOR'S CONSTRUCTION SCHEDULE (GANTT CHART)

- A. Gantt-Chart Schedule: Submit a comprehensive, fully developed, horizontal Gantt-chart-type, Contractor's construction schedule within 30 days of date established for the Notice to Proceed.
- B. Preparation: Indicate each significant construction activity separately. Identify first workday of each week with a continuous vertical line.

2.3 REPORTS

- A. Field Condition Reports: Immediately on discovery of a difference between field conditions and the Contract Documents, prepare and submit a detailed report. Submit with a Request for Information. Include a detailed description of the differing conditions, together with recommendations for changing the Contract Documents.
- B. Progress Reports: At each job progress meeting, submit a typed progress report for inclusion in the meeting minutes. Report shall include a description of work begun/completed since last meeting, a summary work scheduled for the next two weeks, scheduled materials deliveries, and status of submittals, proposal requests, RFI's, etc.

PART 3 - EXECUTION

3.1 CONTRACTOR'S CONSTRUCTION SCHEDULE

- A. Contractor's Construction Schedule Updating: At monthly intervals, update schedule to reflect actual construction progress and activities.
- B. Distribution: Distribute copies of approved schedule to Architect Owner, separate contractors, testing and inspecting agencies, and other parties identified by Contractor with a need-to-know schedule responsibility.
 1. Post copies in Project meeting rooms and temporary field offices.
 2. When revisions are made, distribute updated schedules to the same parties and post in the same locations. Delete parties from distribution when they have completed their assigned portion of the Work and are no longer involved in performance of construction activities.

END OF SECTION 013200

SECTION 013300 - SUBMITTAL PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes requirements for the submittal schedule and administrative and procedural requirements for submitting Shop Drawings, Product Data, Samples, and other submittals.
- B. Related Sections:
 - 1. Division 01 Section "Construction Progress Documentation" for submitting schedules and reports, including Contractor's construction schedule.
 - 2. Division 01 Section "Project Record Documents" for submitting record Drawings.

1.2 DEFINITIONS

- A. Action Submittals: Written and graphic information and physical samples that require Architect's responsive action.
- B. Informational Submittals: Written and graphic information and physical samples that do not require Architect's responsive action. Submittals may be rejected for not complying with requirements.

1.3 SUBMITTAL ADMINISTRATIVE REQUIREMENTS

- A. Architect's Digital Data Files: Electronic copies of CAD Drawings of the Contract Drawings will be provided by Architect for Contractor's use in preparing submittals.
 - 1. Architect will furnish Contractor one set of digital data drawing files of the Contract Drawings for use in preparing Shop Drawings.
 - a. Architect makes no representations as to the accuracy or completeness of digital data drawing files as they relate to the Contract Drawings.
- B. Coordination: Coordinate preparation and processing of submittals with performance of construction activities.
 - 1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.
 - 2. Coordinate transmittal of different types of submittals for related parts of the Work so processing will not be delayed because of need to review submittals concurrently for coordination.
 - a. Architect reserves the right to withhold action on a submittal requiring coordination with other submittals until related submittals are received.

- C. Processing Time: Allow time for submittal review, including time for resubmittals, as follows. Time for review shall commence on Architect's receipt of submittal. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing, including resubmittals.
1. Initial Review: Allow 14 days for initial review of each submittal. Allow additional time if coordination with subsequent submittals is required. Architect will advise Contractor when a submittal being processed must be delayed for coordination.
 2. Intermediate Review: If intermediate submittal is necessary, process it in same manner as initial submittal.
 3. Resubmittal Review: Allow 14 days for review of each resubmittal.
- D. Identification and Information: Place a permanent label or title block on each paper copy submittal item for identification.
1. Indicate name of firm or entity that prepared each submittal on label or title block.
 2. Provide a space approximately 6 by 8 inches on label or beside title block to record Contractor's review and approval markings and action taken by Architect.
 3. Include the following information for processing and recording action taken:
 - a. Project name.
 - b. Date.
 - c. Name of Architect.
 - d. Name of Contractor.
 - e. Name of subcontractor.
 - f. Name of supplier.
 - g. Name of manufacturer.
 - h. Submittal number or other unique identifier, including revision identifier.
 - i. Number and title of appropriate Specification Section.
- E. Options: Identify options requiring selection by the Architect.
- F. Deviations: Identify deviations from the Contract Documents on submittals.
- G. Additional Paper Copies: Unless additional copies are required for final submittal, and unless Architect observes noncompliance with provisions in the Contract Documents, initial submittal may serve as final submittal.
- H. Transmittal: Assemble each submittal individually and appropriately for transmittal and handling. Transmit each submittal using a transmittal form. Architect will discard submittals received from sources other than Contractor.
1. On an attached separate sheet, prepared on Contractor's letterhead, record relevant information, requests for data, revisions other than those requested by Architect on previous submittals, and deviations from requirements in the Contract Documents, including minor variations and limitations. Include same identification information as related submittal.
- I. Resubmittals: Make resubmittals in same form and number of copies as initial submittal.
1. Note date and content of previous submittal.

2. Resubmit submittals until they are marked with approval notation from Architect's action stamp.
- J. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, authorities having jurisdiction, and others as necessary for performance of construction activities. Show distribution on transmittal forms.
- K. Use for Construction: Use only final submittals that are marked with approval notation from Architect's action stamp.

PART 2 - PRODUCTS

2.1 SUBMITTAL PROCEDURES

A. General Submittal Procedure Requirements:

1. Action Submittals: Submit sufficient copies of each submittal to allow Architect to retain three copies, unless otherwise noted.
2. Informational Submittals: Submit two paper copies of each submittal, unless otherwise indicated. Architect will not return copies.
3. Closeout Submittals and Maintenance Material Submittals: Comply with requirements specified in Division 01 Section "Closeout Procedures."
4. Test and Inspection Reports Submittals: Comply with requirements specified in Division 01 Section "Quality Requirements."

B. Product Data: Collect information into a single submittal for each element of construction and type of product or equipment.

1. If information must be specially prepared for submittal because standard published data are not suitable for use, submit as Shop Drawings, not as Product Data.
2. Mark each copy of each submittal to show which products and options are applicable.
3. Include the following information, as applicable:
 - a. Manufacturer's catalog cuts.
 - b. Manufacturer's product specifications.
 - c. Standard color charts.
 - d. Statement of compliance with specified referenced standards.
 - e. Testing by recognized testing agency.
 - f. Application of testing agency labels and seals.
 - g. Notation of coordination requirements.
4. For equipment, include the following in addition to the above, as applicable:
 - a. Wiring diagrams showing factory-installed wiring.
 - b. Printed performance curves.
 - c. Operational range diagrams.
 - d. Clearances required to other construction, if not indicated on accompanying Shop Drawings.

5. Submit Product Data before or concurrent with Samples.
 6. Submit sufficient copies of each submittal to allow Architect to retain three copies, unless otherwise noted.
- C. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data, unless submittal based upon Architect's digital data drawing files is otherwise permitted.
1. Preparation: Fully illustrate requirements in the Contract Documents. Include the following information, as applicable:
 - a. Identification of products.
 - b. Schedules.
 - c. Compliance with specified standards.
 - d. Notation of coordination requirements.
 - e. Notation of dimensions established by field measurement.
 - f. Relationship and attachment to adjoining construction clearly indicated.
 - g. Seal and signature of professional engineer if specified.
 2. Sheet Size: Except for templates, patterns, and similar full-size drawings, submit Shop Drawings on sheets at least 8-1/2 by 11 inches but no larger than 30 by 42 inches.
 3. Submit sufficient copies of each submittal to allow Architect to retain three copies, unless otherwise noted.
- D. Samples: Submit Samples for review of kind, color, pattern, and texture for a check of these characteristics with other elements and for a comparison of these characteristics between submittal and actual component as delivered and installed.
1. Transmit Samples that contain multiple, related components such as accessories together in one submittal package.
 2. Identification: Attach label on unexposed side of Samples that includes the following:
 - a. Generic description of Sample.
 - b. Product name and name of manufacturer.
 - c. Sample source.
 - d. Number and title of applicable Specification Section.
 3. Samples for Initial Selection: Submit manufacturer's color charts consisting of units or sections of units showing the full range of colors, textures, and patterns available.
 - a. Number of Samples: Submit one full set of available choices where color, pattern, texture, or similar characteristics are required to be selected from manufacturer's product line.
 4. Samples for Verification: Submit full-size units or Samples of size indicated, prepared from same material to be used for the Work, cured and finished in manner specified, and physically identical with material or product proposed for use, and that show full range of color and texture variations expected. Samples include, but are not limited to, the following: partial sections of manufactured or fabricated components; small cuts or containers of materials; complete units of repetitively used materials; swatches showing

color, texture, and pattern; color range sets; and components used for independent testing and inspection.

- a. Number of Samples: Submit two sets of Samples. Architect will retain one Sample set; remainder will be returned.
- E. Contractor's Construction Schedule: Comply with requirements specified in Division 01 Section "Construction Progress Documentation."
- F. Application for Payment: Comply with requirements specified in Division 01 Section "Payment Procedures."
- G. Schedule of Values: Comply with requirements specified in Division 01 Section "Payment Procedures."
- H. Subcontract List: Prepare a written summary identifying individuals or firms proposed for each portion of the Work, including those who are to furnish products or equipment fabricated to a special design.
- I. Welding Certificates: Prepare written certification that welding procedures and personnel comply with requirements in the Contract Documents. Submit record of Welding Procedure Specification and Procedure Qualification Record on American Welding Society (AWS) forms. Include names of firms and personnel certified.
- J. Maintenance Data: Comply with requirements specified in Division 01 Section "Operation and Maintenance Data."

PART 3 - EXECUTION

3.1 CONTRACTOR'S REVIEW

- A. Action and Informational Submittals: Review each submittal and check for coordination with other Work of the Contract and for compliance with the Contract Documents. Note corrections and field dimensions. Mark with approval stamp before submitting to Architect.
- B. Project Closeout and Maintenance/Material Submittals: Refer to requirements in Division 01 Section "Closeout Procedures."
- C. Approval Stamp: Stamp each submittal with a uniform, approval stamp. Include Project name and location, submittal number, Specification Section title and number, name of reviewer, date of Contractor's approval, and statement certifying that submittal has been reviewed, checked, and approved for compliance with the Contract Documents.

3.2 ARCHITECT'S ACTION

- A. General: Architect will not review submittals that do not bear Contractor's approval stamp and will return them without action.

- B. Action Submittals: Architect will review each submittal, make marks to indicate corrections or modifications required, and return it. Architect will stamp each submittal with an action stamp and will mark stamp appropriately to indicate action.
- C. Informational Submittals: Architect will review each submittal and will not return it, or will return it if it does not comply with requirements. Architect will forward each submittal to appropriate party.
- D. Incomplete submittals are not acceptable, will be considered nonresponsive, and will be returned without review.
- E. Submittals not required by the Contract Documents may not be reviewed and may be discarded.

END OF SECTION 013300

SECTION 015000 - TEMPORARY FACILITIES AND CONTROLS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes requirements for temporary utilities, support facilities, and security and protection facilities.
- B. Related Section:
 - 1. Division 01 Section "Summary" for work restrictions and limitations on utility interruptions.

1.2 USE CHARGES

- A. General: Installation and removal of and use charges for temporary facilities shall be included in the Contract Sum unless otherwise indicated. Allow other entities to use temporary services and facilities without cost, including, but not limited to, Architect, testing agencies, and authorities having jurisdiction.
- B. Water and Sewer Service from Existing System: Water from Owner's existing water system is available for use without metering and without payment of use charges. Provide connections and extensions of services as required for construction operations.
- C. Electric Power Service from Existing System: Electric power from Owner's existing system is available for use without metering and without payment of use charges. Provide connections and extensions of services as required for construction operations.

1.3 PROJECT CONDITIONS

- A. Temporary Use of Permanent Facilities: Engage installer of each permanent service to assume responsibility for operation, maintenance, and protection of each permanent service during its use as a construction facility before Owner's acceptance, regardless of previously assigned responsibilities.

PART 2 - PRODUCTS

2.1 EQUIPMENT

- A. Fire Extinguishers: Portable, UL rated; with class and extinguishing agent as required by locations and classes of fire exposures.
- B. Lumber and Plywood: Comply with requirements in Division 6 Section "Rough Carpentry".

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Locate facilities where they will serve Project adequately and result in minimum interference with performance of the Work. Relocate and modify facilities as required by progress of the Work.
 - 1. Locate facilities to limit site disturbance as specified in Division 01 Section "Summary."
- B. Provide each facility ready for use when needed to avoid delay. Do not remove until facilities are no longer needed or are replaced by authorized use of completed permanent facilities.

3.2 TEMPORARY UTILITY INSTALLATION

- A. General: Install temporary service or connect to existing service.
- B. Water Service: Connect to Owner's existing water service facilities. Clean and maintain water service facilities in a condition acceptable to Owner. At Substantial Completion, restore these facilities to condition existing before initial use.
- C. Sanitary Facilities: Provide temporary toilets, wash facilities, and drinking water for use of construction personnel. Comply with requirements of authorities having jurisdiction for type, number, location, operation, and maintenance of fixtures and facilities.
- D. Isolation of Work Areas: Prevent dust, fumes, moisture and odors from entering occupied areas.
- E. Electric Power Service: Connect to Owner's existing electric power service. Maintain equipment in a condition acceptable to Owner.

3.3 SUPPORT FACILITIES INSTALLATION

- A. Parking: Use designated areas of Owner's existing parking areas for construction personnel.
- B. Waste Disposal Facilities: Comply with requirements specified in Division 01 Section "Construction Waste Management and Disposal."
- C. Lifts and Hoists: Provide facilities necessary for hoisting materials and personnel.
 - 1. Truck cranes and similar devices used for hoisting materials are considered "tools and equipment" and not temporary facilities.

3.4 SECURITY AND PROTECTION FACILITIES INSTALLATION

- A. Environmental Protection: Provide protection, operate temporary facilities, and conduct construction as required to comply with environmental regulations and that minimize possible air, waterway, and subsoil contamination or pollution or other undesirable effects.

- B. Temporary Fire Protection: Install and maintain temporary fire-protection facilities of types needed to protect against reasonably predictable and controllable fire losses. Comply with NFPA 241.
 - 1. Prohibit smoking in construction areas.
 - 2. Supervise welding operations, combustion-type temporary heating units, and similar sources of fire ignition according to requirements of authorities having jurisdiction.
 - 3. Develop and supervise an overall fire-prevention and -protection program for personnel at Project site. Review needs with local fire department and establish procedures to be followed. Instruct personnel in methods and procedures. Post warnings and information.
- C. Barricades, Warning Signs, and Lights: Comply with requirements of authorities having jurisdiction for erecting structurally adequate barricades, including warning signs and lighting.

3.5 OPERATION, TERMINATION, AND REMOVAL

- A. Supervision: Enforce strict discipline in use of temporary facilities. To minimize waste and abuse, limit availability of temporary facilities to essential and intended uses.
- B. Maintenance: Maintain facilities in good operating condition until removal.
 - 1. Maintain operation of temporary enclosures, heating, ventilation, and similar facilities on a 24-hour basis where required to achieve indicated results and to avoid possibility of damage.
- C. Termination and Removal: Remove each temporary facility when need for its service has ended, when it has been replaced by authorized use of a permanent facility, or no later than Substantial Completion. Complete or, if necessary, restore permanent construction that may have been delayed because of interference with temporary facility. Repair damaged Work, clean exposed surfaces, and replace construction that cannot be satisfactorily repaired.
 - 1. Materials and facilities that constitute temporary facilities are property of Contractor. Owner reserves right to take possession of Project identification signs.
 - 2. At Substantial Completion, repair, renovate, and clean permanent facilities used during construction period. Comply with final cleaning requirements specified in Division 01 Section "Closeout Procedures."

END OF SECTION 015000

SECTION 016000 - PRODUCT REQUIREMENTS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for selection of products for use in Project; product delivery, storage, and handling; manufacturers' standard warranties on products; special warranties; and comparable products.
- B. Related Section:
 - 1. Division 01 Section "Substitution Procedures" for requests for substitutions.

1.2 DEFINITIONS

- A. Products: Items obtained for incorporating into the Work, whether purchased for Project or taken from previously purchased stock. The term "product" includes the terms "material," "equipment," "system," and terms of similar intent.
 - 1. Named Products: Items identified by manufacturer's product name, including make or model number or other designation shown or listed in manufacturer's published product literature, that is current as of date of the Contract Documents.
 - 2. New Products: Items that have not previously been incorporated into another project or facility. Products salvaged or recycled from other projects are not considered new products.
 - 3. Comparable Product: Product that is demonstrated and approved through submittal process to have the indicated qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics that equal or exceed those of specified product.

1.3 ACTION SUBMITTALS

- A. Comparable Product Requests: Submit request for consideration of each comparable product. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
 - 1. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within one week of receipt of a comparable product request. Architect will notify Contractor of approval or rejection of proposed comparable product request within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.
 - a. Form of Approval: As specified in Division 01 Section "Submittal Procedures."
 - b. Use product specified if Architect does not issue a decision on use of a comparable product request within time allocated.

1.4 QUALITY ASSURANCE

- A. Compatibility of Options: If Contractor is given option of selecting between two or more products for use on Project, select product compatible with products previously selected, even if previously selected products were also options.

1.5 PRODUCT DELIVERY, STORAGE, AND HANDLING

- A. Deliver, store, and handle products using means and methods that will prevent damage, deterioration, and loss, including theft and vandalism. Comply with manufacturer's written instructions.
- B. Delivery and Handling:
 - 1. Schedule delivery to minimize long-term storage at Project site and to prevent overcrowding of construction spaces.
 - 2. Coordinate delivery with installation time to ensure minimum holding time for items that are flammable, hazardous, easily damaged, or sensitive to deterioration, theft, and other losses.
 - 3. Deliver products to Project site in an undamaged condition in manufacturer's original sealed container or other packaging system, complete with labels and instructions for handling, storing, unpacking, protecting, and installing.
 - 4. Inspect products on delivery to determine compliance with the Contract Documents and to determine that products are undamaged and properly protected.
- C. Storage:
 - 1. Store products to allow for inspection and measurement of quantity or counting of units.
 - 2. Store materials in a manner that will not endanger Project structure.
 - 3. Store products that are subject to damage by the elements, under cover in a weathertight enclosure above ground, with ventilation adequate to prevent condensation.
 - 4. Store foam plastic from exposure to sunlight, except to extent necessary for period of installation and concealment.
 - 5. Comply with product manufacturer's written instructions for temperature, humidity, ventilation, and weather-protection requirements for storage.
 - 6. Protect stored products from damage and liquids from freezing.

1.6 PRODUCT WARRANTIES

- A. Warranties specified in other Sections shall be in addition to, and run concurrent with, other warranties required by the Contract Documents. Manufacturer's disclaimers and limitations on product warranties do not relieve Contractor of obligations under requirements of the Contract Documents.
 - 1. Manufacturer's Warranty: Written warranty furnished by individual manufacturer for a particular product and specifically endorsed by manufacturer to Owner.
- B. Submittal Time: Comply with requirements in Division 01 Section "Closeout Procedures."

PART 2 - PRODUCTS

2.1 PRODUCT SELECTION PROCEDURES

- A. General Product Requirements: Provide products that comply with the Contract Documents, are undamaged and, unless otherwise indicated, are new at time of installation.
 - 1. Provide products complete with accessories, trim, finish, fasteners, and other items needed for a complete installation and indicated use and effect.
 - 2. Standard Products: If available, and unless custom products or nonstandard options are specified, provide standard products of types that have been produced and used successfully in similar situations on other projects.
 - 3. Owner reserves the right to limit selection to products with warranties not in conflict with requirements of the Contract Documents.
 - 4. Where products are accompanied by the term "as selected," Architect will make selection.
 - 5. Descriptive, performance, and reference standard requirements in the Specifications establish salient characteristics of products.
- B. Product Selection Procedures:
 - 1. Product: Where Specifications name a single manufacturer and product, provide the named product that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
 - 2. Manufacturer/Source: Where Specifications name a single manufacturer or source, provide a product by the named manufacturer or source that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
 - 3. Products:
 - a. Restricted List: Where Specifications include a list of names of both manufacturers and products, provide one of the products listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered, unless otherwise indicated.
 - b. Nonrestricted List: Where Specifications include a list of names of both available manufacturers and products, provide one of the products listed, or an unnamed product, that complies with requirements. Comply with requirements in "Comparable Products" Article for consideration of an unnamed product.
 - 4. Manufacturers:
 - a. Restricted List: Where Specifications include a list of manufacturers' names, provide a product by one of the manufacturers listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered, unless otherwise indicated.
 - b. Nonrestricted List: Where Specifications include a list of available manufacturers, provide a product by one of the manufacturers listed, or a product by an unnamed manufacturer, that complies with requirements. Comply with requirements in "Comparable Products" Article for consideration of an unnamed manufacturer's product.

- C. Visual Selection Specification: Where Specifications include the phrase "as selected by Architect from manufacturer's full range" or similar phrase, select a product that complies with requirements. Architect will select color, gloss, pattern, density, or texture from manufacturer's product line that includes both standard and premium items.

2.2 COMPARABLE PRODUCTS

- A. Conditions for Consideration: Architect will consider Contractor's request for comparable product when the following conditions are satisfied. If the following conditions are not satisfied, Architect may return requests without action, except to record noncompliance with these requirements:
1. Evidence that the proposed product does not require revisions to the Contract Documents, that it is consistent with the Contract Documents and will produce the indicated results, and that it is compatible with other portions of the Work.
 2. Detailed comparison of significant qualities of proposed product with those named in the Specifications. Significant qualities include attributes such as performance, weight, size, durability, visual effect, and specific features and requirements indicated.
 3. Evidence that proposed product provides specified warranty.
 4. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners, if requested.
 5. Samples, if requested.

PART 3 - EXECUTION (Not Used)

END OF SECTION 016000

SECTION 017300 - EXECUTION

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes general administrative and procedural requirements governing execution of the Work including, but not limited to, the following:
 - 1. Construction layout (preparation).
 - 2. Installation of the Work.
 - 3. Cutting and patching.
 - 4. Progress cleaning.
 - 5. Protection of installed construction.
 - 6. Correction of the Work.

1.2 QUALITY ASSURANCE

- A. Cutting and Patching: Comply with requirements for and limitations on cutting and patching of construction elements.
 - 1. Do not cut and patch construction elements or components in a manner that could change their load-carrying capacity, that results in reducing their capacity to perform as intended, or that results in increased maintenance or decreased operational life or safety.
 - 2. Visual Elements: Do not cut and patch construction in a manner that results in visual evidence of cutting and patching. Do not cut and patch exposed construction in a manner that would, in Architect's opinion, reduce the building's aesthetic qualities. Remove and replace construction that has been cut and patched in a visually unsatisfactory manner.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Existing Conditions: The existence and location of utilities and construction indicated as existing are not guaranteed. Before beginning work, investigate and verify the existence and location of utilities, mechanical and electrical systems, and other construction affecting the Work.
- B. Examination and Acceptance of Conditions: Before proceeding with each component of the Work, examine substrates, areas, and conditions, with Installer or Applicator present where indicated, for compliance with requirements for installation tolerances and other conditions affecting performance. Record observations.

1. Verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.
2. Examine roughing-in for mechanical and electrical systems to verify actual locations of connections before equipment and fixture installation.
3. Examine walls, floors, and roofs for suitable conditions where products and systems are to be installed.
4. Proceed with installation only after unsatisfactory conditions have been corrected. Proceeding with the Work indicates acceptance of surfaces and conditions.

3.2 PREPARATION

- A. Field Measurements: Take field measurements as required to fit the Work properly. Recheck measurements before installing each product. Where portions of the Work are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
- B. Space Requirements: Verify space requirements and dimensions of items shown diagrammatically on Drawings.
- C. Review of Contract Documents and Field Conditions: Immediately on discovery of the need for clarification of the Contract Documents caused by differing field conditions outside the control of the Contractor, submit a request for information to Architect according to requirements in Division 01 Section "Project Management and Coordination."

3.3 INSTALLATION

- A. General: Locate the Work and components of the Work accurately, in correct alignment and elevation, as indicated.
 1. Make vertical work plumb and make horizontal work level.
 2. Where space is limited, install components to maximize space available for maintenance and ease of removal for replacement.
- B. Comply with manufacturer's written instructions and recommendations for installing products in applications indicated.
- C. Install products at the time and under conditions that will ensure the best possible results. Maintain conditions required for product performance until Substantial Completion.
- D. Conduct construction operations so no part of the Work is subjected to damaging operations or loading in excess of that expected during normal conditions of occupancy.
- E. Tools and Equipment: Do not use tools or equipment that produce harmful noise levels.
- F. Templates: Obtain and distribute to the parties involved templates for work specified to be factory prepared and field installed. Check Shop Drawings of other work to confirm that adequate provisions are made for locating and installing products to comply with indicated requirements.

- G. Attachment: Provide blocking and attachment plates and anchors and fasteners of adequate size and number to securely anchor each component in place, accurately located and aligned with other portions of the Work. Where size and type of attachments are not indicated, verify size and type required for load conditions.
 - 1. Mounting Heights: Where mounting heights are not indicated, mount components at heights directed by Architect.
 - 2. Allow for building movement, including thermal expansion and contraction.
 - 3. Coordinate installation of anchorages. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors, that are to be embedded in concrete or masonry. Deliver such items to Project site in time for installation.
- H. Joints: Make joints of uniform width. Where joint locations in exposed work are not indicated, arrange joints for the best visual effect. Fit exposed connections together to form hairline joints.
- I. Hazardous Materials: Use products, cleaners, and installation materials that are not considered hazardous.

3.4 CUTTING AND PATCHING

- A. Cutting and Patching, General: Employ skilled workers to perform cutting and patching. Proceed with cutting and patching at the earliest feasible time, and complete without delay.
 - 1. Cut in-place construction to provide for installation of other components or performance of other construction, and subsequently patch as required to restore surfaces to their original condition.
- B. Temporary Support: Provide temporary support of work to be cut.
- C. Protection: Protect in-place construction during cutting and patching to prevent damage. Provide protection from adverse weather conditions for portions of Project that might be exposed during cutting and patching operations.
- D. Adjacent Occupied Areas: Avoid interference with use of adjoining areas or interruption of free passage to adjoining areas.
- E. Existing Utility Services and Mechanical/Electrical Systems: Where existing services/systems are required to be removed, relocated, or abandoned, bypass such services/systems before cutting to prevent interruption to occupied areas.
- F. Cutting: Cut in-place construction by sawing, drilling, breaking, chipping, grinding, and similar operations, including excavation, using methods least likely to damage elements retained or adjoining construction. If possible, review proposed procedures with original Installer; comply with original Installer's written recommendations.
 - 1. In general, use hand or small power tools designed for sawing and grinding, not hammering and chopping. Cut holes and slots neatly to minimum size required, and with minimum disturbance of adjacent surfaces. Temporarily cover openings when not in use.
 - 2. Finished Surfaces: Cut or drill from the exposed or finished side into concealed surfaces.

3. Concrete and Masonry: Cut using a cutting machine, such as an abrasive saw or a diamond-core drill.
 4. Mechanical and Electrical Services: Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit to prevent entrance of moisture or other foreign matter after cutting.
 5. Proceed with patching after construction operations requiring cutting are complete.
- G. Patching: Patch construction by filling, repairing, refinishing, closing up, and similar operations following performance of other work. Patch with durable seams that are as invisible as practicable. Provide materials and comply with installation requirements specified in other Sections, where applicable.
1. Inspection: Where feasible, test and inspect patched areas after completion to demonstrate physical integrity of installation.
 2. Exposed Finishes: Restore exposed finishes of patched areas and extend finish restoration into retained adjoining construction in a manner that will minimize evidence of patching and refinishing.
 3. Floors and Walls: Where walls or partitions that are removed extend one finished area into another, patch and repair floor and wall surfaces in the new space. Provide an even surface of uniform finish, color, texture, and appearance. Remove in-place floor and wall coverings and replace with new materials, if necessary, to achieve uniform color and appearance.
 4. Ceilings: Patch, repair, or rehang in-place ceilings as necessary to provide an even-plane surface of uniform appearance.
- H. Cleaning: Clean areas and spaces where cutting and patching are performed. Remove paint, mortar, oils, putty, and similar materials from adjacent finished surfaces.

3.5 PROGRESS CLEANING

- A. General: Clean Project site and work areas daily, including common areas. Enforce requirements strictly. Dispose of materials lawfully.
1. Comply with requirements in NFPA 241 for removal of combustible waste materials and debris.
 2. Do not hold waste materials more than seven days during normal weather or three days if the temperature is expected to rise above 80 deg F.
 3. Containerize hazardous and unsanitary waste materials separately from other waste. Mark containers appropriately and dispose of legally, according to regulations.
- B. Site: Maintain Project site free of waste materials and debris.
- C. Work Areas: Clean areas where work is in progress to the level of cleanliness necessary for proper execution of the Work.
1. Remove liquid spills promptly.
 2. Where dust would impair proper execution of the Work, broom-clean or vacuum the entire work area, as appropriate.

- D. Installed Work: Keep installed work clean. Clean installed surfaces according to written instructions of manufacturer or fabricator of product installed, using only cleaning materials specifically recommended. If specific cleaning materials are not recommended, use cleaning materials that are not hazardous to health or property and that will not damage exposed surfaces.
- E. Exposed Surfaces in Finished Areas: Clean exposed surfaces and protect as necessary to ensure freedom from damage and deterioration at time of Substantial Completion.
- F. Waste Disposal: Do not bury or burn waste materials on-site. Do not wash waste materials down sewers or into waterways.
- G. During handling and installation, clean and protect construction in progress and adjoining materials already in place. Apply protective covering where required to ensure protection from damage or deterioration at Substantial Completion.
- H. Clean and provide maintenance on completed construction as frequently as necessary through the remainder of the construction period. Adjust and lubricate operable components to ensure operability without damaging effects.
- I. Limiting Exposures: Supervise construction operations to assure that no part of the construction, completed or in progress, is subject to harmful, dangerous, damaging, or otherwise deleterious exposure during the construction period.

3.6 PROTECTION OF INSTALLED CONSTRUCTION

- A. Provide final protection and maintain conditions that ensure installed Work is without damage or deterioration at time of Substantial Completion.
- B. Comply with manufacturer's written instructions for temperature and relative humidity.

3.7 CORRECTION OF THE WORK

- A. Repair or remove and replace defective construction. Restore damaged substrates and finishes.
 - 1. Repairing includes replacing defective parts, refinishing damaged surfaces, touching up with matching materials, and properly adjusting operating equipment.
- B. Restore permanent facilities used during construction to their specified condition.
- C. Remove and replace damaged surfaces that are exposed to view if surfaces cannot be repaired without visible evidence of repair.
- D. Repair components that do not operate properly. Remove and replace operating components that cannot be repaired.

END OF SECTION 017300

SECTION 017419 - CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for the following:

- 1. Disposing of nonhazardous demolition and construction waste.

1.2 DEFINITIONS

- A. Construction Waste: Building and site improvement materials and other solid waste resulting from construction, remodeling, renovation, or repair operations. Construction waste includes packaging.
- B. Demolition Waste: Building and site improvement materials resulting from demolition or selective demolition operations.
- C. Disposal: Removal off-site of demolition and construction waste and subsequent sale, recycling, reuse, or deposit in landfill or incinerator acceptable to authorities having jurisdiction.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 DISPOSAL OF WASTE

- A. General: Except for items or materials to be salvaged, recycled, or otherwise reused, remove waste materials from Project site and legally dispose of them in a landfill or incinerator acceptable to authorities having jurisdiction.
 - 1. Except as otherwise specified, do not allow waste materials that are to be disposed of accumulate on-site.
 - 2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
- B. Burning: Do not burn waste materials.
- C. Disposal: Transport waste materials off Owner's property and legally dispose of them.

END OF SECTION 017419

SECTION 017700 - CLOSEOUT PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for contract closeout, including, but not limited to, the following:
 - 1. Substantial Completion procedures.
 - 2. Final completion procedures.
 - 3. Warranties.
 - 4. Final cleaning.
- B. Related Sections:
 - 1. Division 01 Section "Project Record Documents" for submitting Record Drawings.

1.2 SUBSTANTIAL COMPLETION

- A. Preliminary Procedures: Before requesting inspection for determining date of Substantial Completion, complete the following. List items below that are incomplete with request.
 - 1. Submit specific warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
 - 2. Obtain and submit releases permitting Owner unrestricted use of the Work and access to services and utilities. Include occupancy permits, operating certificates, and similar releases.
 - 3. Prepare and submit Project Record Documents, operation and maintenance manuals, and similar final record information.
 - 4. Terminate and remove temporary facilities, construction tools, and similar elements.
 - 5. Complete final cleaning requirements, including touchup painting.
 - 6. Touch up and otherwise repair and restore marred exposed finishes to eliminate visual defects.
- B. Inspection: Submit a written request for inspection for Substantial Completion. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare the Certificate of Substantial Completion after inspection or will notify Contractor of items, either on Contractor's list or additional items identified by Architect, that must be completed or corrected before certificate will be issued.
 - 1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.
 - 2. Results of completed inspection will form the basis of requirements for final completion.

1.3 FINAL COMPLETION

- A. Preliminary Procedures: Before requesting final inspection for determining final completion, complete the following:
 - 1. Submit a final Application for Payment according to Division 01 Section "Payment Procedures."
- B. Inspection: Submit a written request for final inspection for acceptance. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued.
 - 1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.

1.4 WARRANTIES

- A. Submittal Time: Submit written warranties on request of Architect for designated portions of the Work where commencement of warranties other than date of Substantial Completion is indicated.
- B. Organize warranty documents into an orderly sequence based on the table of contents of the Project Manual.
 - 1. Bind warranties and bonds in heavy-duty, 3-ring, vinyl-covered, loose-leaf binders, thickness as necessary to accommodate contents, and sized to receive 8-1/2-by-11-inch paper.
 - 2. Provide heavy paper dividers with plastic-covered tabs for each separate warranty. Mark tab to identify the product or installation. Provide a typed description of the product or installation, including the name of the product and the name, address, and telephone number of Installer.
 - 3. Identify each binder on the front and spine with the typed or printed title "WARRANTIES," Project name, and name of Contractor.
- C. Provide additional copies of each warranty to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.

PART 3 - EXECUTION

3.1 FINAL CLEANING

- A. General: Perform final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations.
- B. Cleaning: Employ experienced workers for final cleaning.
 - 1. Complete the following cleaning operations before requesting inspection for certification of Substantial Completion for entire Project or for a portion of Project:
 - a. Clean Project site, yard, and grounds, in areas disturbed by construction activities, of rubbish, waste material, litter, and other foreign substances.
 - b. Sweep paved areas broom clean. Remove petrochemical spills, stains, and other foreign deposits.
 - c. Remove tools, construction equipment, machinery, and surplus material from Project site.
 - d. Sweep all roof areas and remove all construction debris prior to substantial completion inspection.
- C. Construction Waste Disposal: Comply with waste disposal requirements in Division 01 Section "Construction Waste Management and Disposal."

END OF SECTION 017700

SECTION 017839 - PROJECT RECORD DOCUMENTS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for project record documents, including the following:

- 1. Record Drawings.

1.2 CLOSEOUT SUBMITTALS

- A. Record Drawings: Comply with the following:

- 1. Number of Copies: Submit one set of marked-up record prints.

PART 2 - PRODUCTS

2.1 RECORD DRAWINGS

- A. Record Prints: Maintain one set of marked-up paper copies of the Contract Drawings and Shop Drawings.

- 1. Preparation: Mark record prints to show the actual installation where installation varies from that shown originally. Require individual or entity who obtained record data, whether individual or entity is Installer, subcontractor, or similar entity, to provide information for preparation of corresponding marked-up record prints.
 - a. Give particular attention to information on concealed elements that would be difficult to identify or measure and record later.
 - b. Record data as soon as possible after obtaining it.
 - c. Record and check the markup before enclosing concealed installations.
 - 2. Mark the Contract Drawings and Shop Drawings completely and accurately. Utilize personnel proficient at recording graphic information in production of marked-up record prints.
 - 3. Mark record sets with erasable, red-colored pencil. Use other colors to distinguish between changes for different categories of the Work at same location.
 - 4. Note Construction Change Directive numbers, alternate numbers, Change Order numbers, and similar identification, where applicable.

- B. Format: Identify and date each record Drawing; include the designation "PROJECT RECORD DRAWING" in a prominent location.

1. Record Prints: Organize record prints and newly prepared record Drawings into manageable sets. Bind each set with durable paper cover sheets. Include identification on cover sheets.
2. Identification: As follows:
 - a. Project name.
 - b. Date.
 - c. Designation "PROJECT RECORD DRAWINGS."
 - d. Name of Architect.
 - e. Name of Contractor.

2.2 MISCELLANEOUS RECORD SUBMITTALS

- A. Assemble miscellaneous records required by other Specification Sections for miscellaneous record keeping and submittal in connection with actual performance of the Work. Bind or file miscellaneous records and identify each, ready for continued use and reference.

PART 3 - EXECUTION

3.1 RECORDING AND MAINTENANCE

- A. Maintenance of Record Documents and Samples: Store record documents and Samples in the field office apart from the Contract Documents used for construction. Do not use project record documents for construction purposes. Maintain record documents in good order and in a clean, dry, legible condition, protected from deterioration and loss. Provide access to project record documents for Architect's reference during normal working hours.

END OF SECTION 017839

SECTION 061000 - ROUGH CARPENTRY

PART 1 - GENERAL

1.1 SUMMARY

- A. This Section includes the following:
 - 1. Wood blocking and nailers.
- B. Related Sections include the following:
 - 1. Division 7 Section "Ethylene-Propylene-Diene-Monomel (EPDM) Roofing".
 - 2. Division 7 Section "Sheet Metal Flashing and Trim".

1.2 DEFINITIONS

- A. Rough Carpentry: Carpentry work not specified in other Sections and not exposed, unless otherwise indicated.

1.3 SUBMITTALS

- A. Product Data: For each type of process and factory-fabricated product. Indicate component materials and dimensions and include construction and application details.
 - 1. Include data for wood-preservative treatment from chemical treatment manufacturer and certification by treating plant that treated materials comply with requirements. Indicate type of preservative used, net amount of preservative retained, and chemical treatment manufacturer's written instructions for handling, storing, installing, and finishing treated material.
 - 2. Include data for fire-retardant treatment from chemical treatment manufacturer and certification by treating plant that treated materials comply with requirements. Include physical properties of treated materials, both before and after exposure to elevated temperatures when tested according to ASTM D 5516 and ASTM D 5664.
 - 3. For products receiving a waterborne treatment, include statement that moisture content of treated materials was reduced to levels specified before shipment to Project site.
 - 4. Include copies of warranties from chemical treatment manufacturers for each type of treatment.
- B. Research/Evaluation Reports: For the following, showing compliance with building code in effect for Project:
 - 1. Preservative-treated wood.
 - 2. Fire-retardant-treated wood.

1.4 QUALITY ASSURANCE

- A. Source Limitations for Fire-Retardant-Treated Wood: Obtain each type of fire-retardant-treated wood product through one source from a single producer.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Stack lumber, plywood, and other panels; place spacers between each bundle to provide air circulation. Provide for air circulation around stacks and under coverings.

PART 2 - PRODUCTS

2.1 WOOD PRODUCTS, GENERAL

- A. Lumber: DOC PS 20 and applicable rules of lumber grading agencies certified by the American Lumber Standards Committee Board of Review.
 - 1. Provide dressed lumber, S4S, unless otherwise indicated.
 - 2. Provide dry lumber with 19 percent maximum moisture content at time of dressing for 2-inch nominal thickness or less, unless otherwise indicated.

2.2 WOOD-PRESERVATIVE-TREATED MATERIALS

- A. Preservative Treatment by Pressure Process: AWPAC2 (lumber) and AWPAC9 (plywood), except that lumber that is not in contact with the ground and is continuously protected from liquid water may be treated according to AWPAC31 with inorganic boron (SBX).
 - 1. Preservative Chemicals: Acceptable to authorities having jurisdiction and one of the following:
 - a. Chromated copper arsenate (CCA).
 - b. Ammoniacal copper zinc arsenate (ACZA).
 - c. Ammoniacal, or amine, copper quat (ACQ).
 - d. Copper bis (dimethyldithiocarbamate) (CDDC).
 - e. Ammoniacal copper citrate (CC).
 - f. Copper azole, Type A (CBA-A).
 - g. Oxine copper (copper-8-quinolinolate) in a light petroleum solvent.
- B. Kiln-dry material after treatment to a maximum moisture content of 19 percent for lumber. Do not use material that is warped or does not comply with requirements for untreated material.
- C. Mark each treated item with the treatment quality mark of an inspection agency approved by the American Lumber Standards Committee Board of Review.
- D. Application: Treat all rough carpentry, unless otherwise indicated.

2.3 FIRE-RETARDANT-TREATED MATERIALS

- A. General: Where fire-retardant-treated materials are indicated, use materials complying with requirements in this article, that are acceptable to authorities having jurisdiction, and with fire-test-response characteristics specified as determined by testing identical products per test method indicated by a qualified testing agency.
- B. Fire-Retardant-Treated Lumber and Plywood by Pressure Process: Products with a flame spread index of 25 or less when tested according to ASTM E 84, and with no evidence of significant progressive combustion when the test is extended an additional 20 minutes, and with the flame front not extending more than 10.5 feet beyond the centerline of the burners at any time during the test.
 - 1. Use treatment that does not promote corrosion of metal fasteners.
 - 2. Interior Type A: Treated materials shall have a moisture content of 28 percent or less when tested according to ASTM D 3201 at 92 percent relative humidity. Use where exterior type is not indicated.
- C. Identify fire-retardant-treated wood with appropriate classification marking of qualified testing agency.

2.4 MISCELLANEOUS LUMBER

- A. General: Provide lumber for support or attachment of other construction, including the following:
 - 1. Blocking.
 - 2. Nailers.
- B. For items of dimension lumber size, provide Construction, Stud, or No. 2 grade lumber with 19 percent maximum moisture content and any of the following species:
 - 1. Mixed southern pine; SPIB.
 - 2. Hem-fir or Hem-fir (north); NLGA, WCLIB, or WWPA.
 - 3. Spruce-pine-fir (south) or Spruce-pine-fir; NELMA, NLGA, WCLIB, or WWPA.
 - 4. Eastern softwoods; NELMA.
 - 5. Northern species; NLGA.
 - 6. Western woods; WCLIB or WWPA.
- C. For concealed boards, provide lumber with 19 percent maximum moisture content and any of the following species and grades:
 - 1. Mixed southern pine, No. 2 grade; SPIB.
 - 2. Hem-fir or Hem-fir (north), Construction or 2 Common grade; NLGA, WCLIB, or WWPA.
 - 3. Spruce-pine-fir (south) or Spruce-pine-fir, Construction or 2 Common grade; NELMA, NLGA, WCLIB, or WWPA.
 - 4. Eastern softwoods, No. 2 Common grade; NELMA.
 - 5. Northern species, No. 2 Common grade; NLGA.
 - 6. Western woods, Construction or No. 2 Common grade; WCLIB or WWPA.

2.5 FASTENERS

- A. General: Provide fasteners of size and type indicated that comply with requirements specified in this Article for material and manufacture.
 - 1. Where rough carpentry is exposed to weather, in ground contact, or in area of high relative humidity, provide fasteners with hot-dip zinc coating complying with ASTM A 153/A 153M.
- B. Nails, Brads, and Staples: ASTM F 1667.
- C. Power-Driven Fasteners: CABO NER-272.
- D. Wood Screws: ASME B18.6.1.
- E. Bolts: Steel bolts complying with ASTM A 307, Grade A; with ASTM A 563 hex nuts and, where indicated, flat washers.
- F. Expansion Anchors: Anchor bolt and sleeve assembly of material indicated below with capability to sustain, without failure, a load equal to 6 times the load imposed when installed in unit masonry assemblies and equal to 4 times the load imposed when installed in concrete as determined by testing per ASTM E 488 conducted by a qualified independent testing and inspecting agency.
 - 1. Material: Carbon-steel components, zinc plated to comply with ASTM B 633, Class Fe/Zn 5.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL

- A. Set rough carpentry to required levels and lines, with members plumb, true to line, cut, and fitted. Fit rough carpentry to other construction; scribe and cope as needed for accurate fit. Locate nailers, blocking, and similar supports to comply with requirements for attaching other construction.
- B. Do not use materials with defects that impair quality of rough carpentry or pieces that are too small to use with minimum number of joints or optimum joint arrangement.
- C. Apply field treatment complying with AWP A M4 to cut surfaces of preservative-treated lumber and plywood.
- D. Securely attach rough carpentry work to substrate by anchoring and fastening as indicated, complying with the following:
 - 1. Table 2305.2, "Fastening Schedule," in the BOCA National Building Code.
- E. Use common wire nails, unless otherwise indicated. Select fasteners of size that will not fully penetrate members where opposite side will be exposed to view or will receive finish materials.

Make tight connections between members. Install fasteners without splitting wood; predrill as required.

3.2 WOOD BLOCKING AND NAILER INSTALLATION

- A. Install where indicated and where required for attaching other work. Form to shapes indicated and cut as required for true line and level of attached work. Coordinate locations with other work involved.
- B. Attach items to substrates to support applied loading. Recess bolts and nuts flush with surfaces, unless otherwise indicated. Build anchor bolts into masonry during installation of masonry work. Where possible, secure anchor bolts to formwork before concrete placement.

END OF SECTION 061000

SECTION 075323 - ETHYLENE-PROPYLENE-DIENE-MONOMER (EPDM) ROOFING

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Adhered EPDM membrane roofing system.
2. Roof insulation.

B. Related Sections:

1. Division 06 Section "Rough Carpentry" for wood nailers, curbs, and blocking.
2. Division 07 Section "Sheet Metal Flashing and Trim" for sheet metal fabrications.

1.2 DEFINITIONS

- A. Roofing Terminology: See ASTM D 1079 and glossary of NRCA's "The NRCA Roofing and Waterproofing Manual" for definitions of terms related to roofing work in this Section.

1.3 PERFORMANCE REQUIREMENTS

- A. General Performance: Installed membrane roofing and base flashings shall withstand specified uplift pressures, thermally induced movement, and exposure to weather without failure due to defective manufacture, fabrication, installation, or other defects in construction. Membrane roofing and base flashings shall remain watertight.
- B. Material Compatibility: Provide roofing materials that are compatible with one another under conditions of service and application required, as demonstrated by membrane roofing manufacturer based on testing and field experience.
- C. Roofing System Design: Provide membrane roofing system that is identical to systems that have been successfully tested by a qualified testing and inspecting agency to resist uplift pressure calculated according to ASCE/SEI 7.
1. Corner Uplift Pressure: 45 PSF
 2. Perimeter Uplift Pressure: 35 PSF
 3. Field-of-Roof Uplift Pressure: 19 PSF

1.4 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Shop Drawings: For roofing system. Include plans, elevations, sections, details, and attachments to other work, including:

1. Base flashings and membrane terminations.
 2. Tapered insulation, including slopes.
 3. Insulation fastening patterns for corner, perimeter, and field-of-roof locations.
 4. EPDM sheet layout.
- C. Samples for Verification: For the following products, in manufacturer's standard sizes:
1. Sheet roofing.
 2. Roof insulation.
 3. Termination bars.
 4. Two insulation fasteners of each type, length, and finish.
- D. Qualification Data: For qualified Installer and manufacturer.
- E. Manufacturer Certificate: Signed by roofing manufacturer certifying that membrane roofing system complies with requirements specified in "Performance Requirements" Article.
1. Submit evidence of complying with performance requirements.
- F. Product Test Reports: Based on evaluation of comprehensive tests performed by manufacturer and witnessed by a qualified testing agency, for components of membrane roofing system.
- G. Research/Evaluation Reports: For components of membrane roofing system.
- H. Field quality-control reports.
- I. Maintenance Data: For membrane roofing system to include in maintenance manuals.
- J. Warranties: Sample of special warranties.

1.5 QUALITY ASSURANCE

- A. Manufacturer Qualifications: A qualified manufacturer that is UL listed for membrane roofing system identical to that used for this Project.
- B. Installer Qualifications: A qualified firm that is approved, authorized, or licensed by membrane roofing system manufacturer to install manufacturer's product and that is eligible to receive manufacturer's special warranty.
- C. Source Limitations: Obtain components including roof insulation and fasteners for membrane roofing system from same manufacturer as membrane roofing.
- D. Exterior Fire-Test Exposure: ASTM E 108, Class A; for application and roof slopes indicated, as determined by testing identical membrane roofing materials by a qualified testing agency. Materials shall be identified with appropriate markings of applicable testing agency.
- E. Preinstallation Roofing Conference: Conduct conference at Project site.
1. Meet with Owner, Architect, Owner's insurer if applicable, testing and inspecting agency representative, roofing Installer, roofing system manufacturer's representative, deck

- Installer, and installers whose work interfaces with or affects roofing, including installers of roof accessories and roof-mounted equipment.
2. Review methods and procedures related to roofing installation, including manufacturer's written instructions.
 3. Review and finalize construction schedule and verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
 4. Examine deck substrate conditions and finishes for compliance with requirements, including flatness and fastening.
 5. Review structural loading limitations of roof deck during and after roofing.
 6. Review base flashings, special roofing details, roof drainage, roof penetrations, equipment curbs, and condition of other construction that will affect roofing system.
 7. Review governing regulations and requirements for insurance and certificates if applicable.
 8. Review temporary protection requirements for roofing system during and after installation.
 9. Review roof observation and repair procedures after roofing installation.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Deliver roofing materials to Project site in original containers with seals unbroken and labeled with manufacturer's name, product brand name and type, date of manufacture, approval or listing agency markings, and directions for storing and mixing with other components.
- B. Store liquid materials in their original undamaged containers in a clean, dry, protected location and within the temperature range required by roofing system manufacturer. Protect stored liquid material from direct sunlight.
 1. Discard and legally dispose of liquid material that cannot be applied within its stated shelf life.
- C. Protect roof insulation materials from physical damage and from deterioration by sunlight, moisture, soiling, and other sources. Store in a dry location. Comply with insulation manufacturer's written instructions for handling, storing, and protecting during installation.
- D. Handle and store roofing materials and place equipment in a manner to avoid permanent deflection of deck.

1.7 PROJECT CONDITIONS

- A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit roofing system to be installed according to manufacturer's written instructions and warranty requirements.

1.8 WARRANTY

- A. Special Warranty: Manufacturer's standard or customized form, without monetary limitation, in which manufacturer agrees to repair or replace components of membrane roofing system that fail in materials or workmanship within specified warranty period.

1. Special warranty includes membrane roofing, base flashings, roof insulation, fasteners, roofing accessories, and other components of membrane roofing system.
 2. Warranty Period: 20 years from date of Substantial Completion of the entire project.
 3. Warranty to include a maximum peak gust wind of 72 MPH.
 4. Provide manufacturer extended membrane material warranty.
- B. Special Project Warranty: Submit roofing Installer's warranty, signed by Installer, covering Work of this Section, including all components of membrane roofing system such as membrane roofing, base flashing, roof insulation, fasteners, walkway products, etc. for the following warranty period:
1. Warranty Period: Two years from date of Substantial Completion of the entire project.

PART 2 - PRODUCTS

2.1 EPDM MEMBRANE ROOFING

- A. EPDM: ASTM D 4637, Type II, scrim or fabric internally reinforced, flexible EPDM sheet.
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - a. Carlisle SynTec Incorporated.
 - b. Firestone Building Products.
 - c. Johns Manville
 2. Thickness: 60 mils, nominal.
 3. Exposed Face Color: Black
 4. Sheet Size: 10' x 100' or largest sheet possible as determined by job conditions.
 5. Factory-applied seam tape.

2.2 AUXILIARY MEMBRANE ROOFING MATERIALS

- A. General: Auxiliary membrane roofing materials recommended by roofing system manufacturer for intended use and compatible with membrane roofing.
1. Liquid-type auxiliary materials shall comply with VOC limits of authorities having jurisdiction.
 2. Adhesives and sealants that are not on the exterior side of weather barrier shall comply with the following limits for VOC content:
 - a. Plastic Foam Adhesives: 50 g/L.
 - b. Multipurpose Construction Adhesives: 70 g/L.
 - c. Fiberglass Adhesives: 80 g/L.
 - d. Single-Ply Membrane Adhesive: 250 g/L.
 - e. Single-Ply Roof Membrane Sealants: 450 g/L.
 - f. Nonmembrane Roof Sealants: 300 g/L.
 - g. Sealant Primers for Nonporous Substrates: 250 g/L.

- h. Sealant Primers for Porous Substrates: 775 g/L.
 - i. Other Adhesives and Sealants: 250 g/L.
- B. Sheet Flashing: 60-mil- thick EPDM, partially cured or cured, according to application.
- C. Bonding Adhesive: Manufacturer's standard, Low-VOC Bonding Adhesive.
- D. Seaming Material: Manufacturer's standard, synthetic-rubber polymer primer and 3-inch- wide minimum, butyl splice tape with release film.
- E. Lap Sealant: Manufacturer's standard, single-component sealant, colored to match membrane roofing.
- F. Water Cutoff Mastic: Manufacturer's standard butyl mastic sealant.
- G. Metal Termination Bars: Manufacturer's standard, predrilled stainless-steel or aluminum bars, approximately 1 by 1/8 inch thick; with anchors.
- H. Fasteners: Heavy-Duty HP factory-coated steel fasteners and metal or plastic plates complying with corrosion-resistant provisions in FM Global 4470; designed for fastening insulation and membrane to the existing metal deck, and acceptable to roofing system manufacturer.
- I. Miscellaneous Accessories: Provide pourable sealers, preformed cone and vent sheet flashings, preformed inside and outside corner sheet flashings, reinforced EPDM securement strips, T-joint covers, in-seam sealants, termination reglets, cover strips, and other accessories.

2.3 ROOF INSULATION

- A. General: Preformed roof insulation boards manufactured or approved by EPDM membrane roofing manufacturer, selected from manufacturer's standard sizes suitable for application, of thicknesses indicated.
- B. Polyisocyanurate Board Insulation: ASTM C 1289, Type II, Class I, Grade 3, glass-fiber mat facer on both major surfaces, compressive strength 25 psi, nominal, insulation shall comply with FM-4450 for installation on metal deck without a thermal barrier.
 - 1. Manufacturers subject to compliance with requirements, provide products by one of the following:
 - a. Atlas Roofing Corporation
 - b. Carlisle SynTec Incorporated
 - c. Firestone Building Products Company
 - d. Johns Manville
- C. Flat Insulation Thickness:
 - 1. 4" thick.

2.4 INSULATION ACCESSORIES

- A. General: Furnish roof insulation accessories recommended by insulation manufacturer for intended use and compatibility with membrane roofing.

- B. Fasteners (Metal Deck on Roof Section 100): Heavy-Duty HP factory-coated steel fasteners and metal or plastic plates complying with corrosion-resistance provisions in FM Global 4470, designed for fastening roof insulation to existing metal deck, and acceptable to roofing manufacturer. Provide one fastener for every 2 SF of insulation or more if required by manufacturer.
 - 1. Contractor to conduct pull out test to verify proposed fastener meets roof material manufacturers pull out resistance.
- C. Insulation Adhesive (Metal Deck on Roof Section 101 – Elevator Shaft): Insulation manufacturer's recommended adhesive formulated to attach roof insulation to substrate or to another insulation layer as follows:
 - 1. Bead-Applied (4" spacing), low-rise, two-component urethane adhesive.

2.5 WALK PADS

- A. Factory-formed, non-porous, heavy duty, solid-rubber, slip resistant, surface textured walkway pads (30"x30"), 3/16 inch thick and acceptable to roof system manufacturer spaced min. 3" apart.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with the following requirements and other conditions affecting performance of roofing system:
 - 1. Verify that roof openings and penetrations are in place and curbs are set and braced and that roof drain bodies are securely clamped in place.
 - 2. Verify that wood blocking, curbs, and nailers are securely anchored to roof deck at penetrations and terminations and that nailers match thicknesses of insulation.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Clean substrate of dust, debris, moisture, and other substances detrimental to roofing installation according to roofing system manufacturer's written instructions. Remove sharp projections.
 - 1. The surface to which the adhesive is to be applied shall be smooth, dry, free of fins, sharp edges, loose and foreign materials, oils and grease and standing water. All sharp projections and loose materials shall be removed by sweeping, blowing, or vacuum cleaning. Previously unexposed asphalt must be primed.
- B. Prevent materials from entering and clogging roof drains and conductors and from spilling or migrating onto surfaces of other construction. Remove roof-drain plugs when no work is taking place or when rain is forecast.

- C. Complete terminations and base flashings and provide temporary seals to prevent water from entering completed sections of roofing system at the end of the workday or when rain is forecast. Remove and discard temporary seals before beginning work on adjoining roofing.
- D. Install roofing and auxiliary materials to tie into existing roofing to maintain water tightness of transition.

3.3 INSULATION INSTALLATION

- A. Coordinate installing membrane roofing system components so insulation is not exposed to precipitation or left exposed at the end of the workday.
- B. Comply with membrane roofing system and insulation manufacturer's written instructions for installing roof insulation.
- C. Trim surface of insulation where necessary at roof drains so completed surface is flush and does not restrict flow of water.
- D. Install insulation with long joints of insulation in a continuous straight line with end joints staggered between rows, abutting edges and ends between boards. Fill gaps exceeding 1/4 inch (6 mm) with insulation.
 - 1. Cut and fit insulation within 1/4 inch of nailers, projections, and penetrations.
- E. Mechanically Fastened Insulation (Metal Deck on Roof Section 100): Install each layer of insulation and secure to deck using mechanical fasteners specifically designed and sized for fastening specified board type roof insulation to deck type.
 - 1. Fasten insulation to resist uplift pressure at corners, perimeter, and field of roof.
- F. Adhered Insulation (Metal Deck on Roof Section 101 – Elevator Shaft): Install each layer of insulation and adhere to substrate as follows:
 - 1. Bead-Applied: Set each layer of insulation in ribbons (spaced 4” apart) of bead-applied insulation adhesive, firmly pressing and maintaining insulation in place.

3.4 ADHERED MEMBRANE ROOFING INSTALLATION

- A. Adhere membrane roofing over area to receive roofing according to membrane roofing system manufacturer's written instructions. Unroll membrane roofing and allow to relax before installing.
- B. Accurately align membrane roofing and maintain uniform side and end laps of minimum dimensions required by manufacturer. Stagger end laps.
- C. Bonding Adhesive: Apply to substrate and underside of membrane roofing at rate required by manufacturer and allow to partially dry before installing membrane roofing. Do not apply to splice area of membrane roofing.
- D. In addition to adhering, mechanically fasten membrane roofing securely at terminations, penetrations, and perimeters.

- E. Apply membrane roofing with side laps shingled with slope of roof deck where possible.
- F. Factory-Applied Seam Tape Installation: Clean and prime surface to receive tape and firmly roll side and end laps of overlapping roof membrane according to manufacturer's written instructions to ensure a watertight seam installation. Apply lap sealant and seal exposed edges of membrane roofing terminations.
- G. Install 6" wide EPDM cover strip with butyl splice tape over all horizontal and vertical field fabricated seam (3" wide lap and 6" wide cover strip).
- H. Repair tears, voids, and lapped seams in roofing that does not comply with requirements.
- I. Spread sealant or mastic bed over deck drain flange at roof drains and securely seal membrane roofing in place with clamping ring.

3.5 BASE FLASHING INSTALLATION

- A. Install sheet flashings and preformed flashing accessories and adhere to substrates according to membrane roofing system manufacturer's written instructions.
- B. Apply bonding adhesive to substrate and underside of sheet flashing at required rate and allow to partially dry. Do not apply to seam area of flashing.
- C. Flash penetrations and field-formed inside and outside corners with cured or uncured sheet flashing.
- D. Clean splice areas, apply splicing cement, and firmly roll side and end laps of overlapping sheets to ensure a watertight seam installation. Apply lap sealant and seal exposed edges of sheet flashing terminations.
- E. Terminate and seal top of sheet flashings and mechanically anchor to substrate through termination bars.

3.6 WALK PAD INSTALLATION

- A. Flexible Walkways: Install walk pads in locations indicated. Adhere walk pads to substrate with compatible adhesive according to roofing system manufacturer's written instructions.
 - 1. Fully adhere walk pad to roof membrane and install lap sealant around entire perimeter.

3.7 DAILY SEAL: Extreme care should be exercised to ensure that the water does not flow beneath any completed sections of roof. Temporarily seal loose edge of membrane with manufacturer approved materials regardless of weather conditions.

- A. Proposed daily tie-in procedure and materials shall be reviewed and approved by Owner/Architect at Pre-Construction Conference.
- B. Roof substrate surface shall be clean and dry.

- C. After embedding membrane in approved seal, check for continuous contact. Then weight the edge, providing continuous pressure over the length of the cutoff. The recommended weight for the continuous pressure is a ten foot length of 2-1/2 inch Lay Flat Tubing filled with dry sand.
- D. When work is resumed, pull sheet free before continuing installation.

3.8 FIELD QUALITY CONTROL

- A. Final Roof Inspection: Arrange for roofing system manufacturer's technical personnel to inspect roofing installation on completion.
- B. Repair or remove and replace components of membrane roofing system where inspections indicate that they do not comply with specified requirements.
- C. Additional inspections, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.

3.9 PROTECTING AND CLEANING

- A. Protect membrane roofing system from damage and wear during remainder of construction period. When remaining construction will not affect or endanger roofing, inspect roofing for deterioration and damage, describing its nature and extent in a written report, with copies to Architect and Owner.
- B. Correct deficiencies in or remove membrane roofing system that does not comply with requirements, repair substrates and repair or reinstall membrane roofing system to a condition free of damage and deterioration at time of Substantial Completion and according to warranty requirements.
- C. Clean overspray and spillage from adjacent construction using cleaning agents and procedures recommended by manufacturer of affected construction.

END OF SECTION 075323

SECTION 076200 - SHEET METAL FLASHING AND TRIM

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:

- 1. Formed Products:

- a. Formed low-slope roof and roof drainage sheet metal fabrications.
 - b. Miscellaneous sheet metal fabrications.

- B. Related Sections:

- 1. Division 06 Section "Rough Carpentry" for wood nailers, curbs, and blocking.
 - 2. Division 07 Section "Ethylene-Propylene-Diene-Monomer (EPDM) Roofing" for installing sheet metal flashing and trim integral with membrane roofing.

1.3 PERFORMANCE REQUIREMENTS

- A. General: Sheet metal flashing and trim assemblies as indicated shall withstand wind loads, structural movement, thermally induced movement, and exposure to weather without failure due to defective manufacture, fabrication, installation, or other defects in construction. Completed sheet metal flashing and trim shall not rattle, leak, or loosen, and shall remain watertight.
- B. Thermal Movements: Provide sheet metal flashing and trim that allows for thermal movements from ambient and surface temperature changes.
 - 1. Temperature Change (Range): 120 deg F (67 deg C), ambient; 180 deg F (100 deg C), material surfaces.

1.4 SUBMITTALS

- A. Product Data: For each type of product indicated. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for each manufactured product and accessory.
- B. Shop Drawings: Show fabrication and installation layouts of sheet metal flashing and trim, including plans, elevations, expansion-joint locations, and keyed details. Distinguish between shop- and field-assembled work. Include the following:

1. Identification of material, thickness, weight, and finish for each item and location in Project.
2. Details for forming sheet metal flashing and trim, including profiles, shapes, seams, and dimensions.
3. Details for joining, supporting, and securing sheet metal flashing and trim, including layout of fasteners, cleats, clips, and other attachments. Include pattern of seams.
4. Details of termination points and assemblies, including fixed points.
5. Details of expansion joints and expansion-joint covers, including showing direction of expansion and contraction.
6. Details of edge conditions, including eaves, ridges, valleys, rakes, crickets, and counterflashings as applicable.
7. Details of special conditions.
8. Details of connections to adjoining work.
9. Detail formed flashing and trim at a scale of not less than 1-1/2 inches per 12 inches.

C. Qualification Data: For qualified fabricator.

D. Maintenance Data: For sheet metal flashing, trim, and accessories to include in maintenance manuals.

1.5 QUALITY ASSURANCE

- A. Fabricator Qualifications: Shop that employs skilled workers who custom fabricate sheet metal flashing and trim similar to that required for this Project and whose products have a record of successful in-service performance.
- B. Sheet Metal Flashing and Trim Standard: Comply with SMACNA's "Architectural Sheet Metal Manual" unless more stringent requirements are specified or shown on Drawings.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Do not store sheet metal flashing and trim materials in contact with other materials that might cause staining, denting, or other surface damage. Store sheet metal flashing and trim materials away from uncured concrete and masonry.
- B. Protect strippable protective covering on sheet metal flashing and trim from exposure to sunlight and high humidity, except to the extent necessary for the period of sheet metal flashing and trim installation.

PART 2 - PRODUCTS

2.1 SHEET METALS

- A. General: Protect mechanical and other finishes on exposed surfaces from damage by applying a strippable, temporary protective film before shipping.

- B. Aluminum Sheet: ASTM B 209 (ASTM B 209M), Alloy as standard with manufacturing for finish required with temper as required to suit forming operations and performance required; with smooth, flat surface.
 - 1. Exposed Coil – Coated Finish:
 - a. Two Coat Fluoropolymer: AAMA 620, Fluoropolymer finish containing not less than 70 percent PVDF resin by weight in color coat. Prepare, pretreat, and apply coating to exposed metal surfaces to comply with coating and resin manufacturer's written instructions.
 - b. Color: As selected by Architect from manufacturer's full range.

2.2 UNDERLAYMENT MATERIALS

- A. Felt: ASTM D 226, Type II (No. 30), asphalt-saturated organic felt, nonperforated.

2.3 MISCELLANEOUS MATERIALS

- A. General: Provide materials and types of fasteners, solder, welding rods, protective coatings, separators, sealants, and other miscellaneous items as required for complete sheet metal flashing and trim installation and recommended by manufacturer of primary sheet metal unless otherwise indicated.
- B. Fasteners: Wood screws, annular threaded nails, self-tapping screws, self-locking rivets and bolts, and other suitable fasteners designed to withstand design loads and recommended by manufacturer of primary sheet metal.
 - 1. General: Blind fasteners or self-drilling screws, gasketed, with hex-washer head.
 - a. Exposed Fasteners: Heads matching color of sheet metal using plastic caps or factory-applied coating.
 - b. Blind Fasteners: High-strength aluminum or stainless-steel rivets suitable for metal being fastened.
 - c. Spikes and Ferrules: Same material as gutter; with spike with ferrule matching internal gutter width.
- C. Solder:
 - 1. For Copper: ASTM B 32, Grade Sn50, 50 percent tin and 50 percent lead.
- D. Sealant Tape: Pressure-sensitive, 100 percent solids, gray polyisobutylene compound sealant tape with release-paper backing. Provide permanently elastic, nonsag, nontoxic, nonstaining tape 1/2 inch (13 mm) wide and 1/8 inch (3 mm) thick.
- E. Elastomeric Sealant: ASTM C 920, elastomeric polyurethane polymer sealant; low modulus; of type, grade, class, and use classifications required to seal joints in sheet metal flashing and trim and remain watertight.
- F. Epoxy Seam Sealer: Two-part, noncorrosive, aluminum seam-cementing compound, recommended by aluminum manufacturer for exterior nonmoving joints, including riveted joints.

- G. Bituminous Coating: Cold-applied asphalt emulsion complying with ASTM D 1187.
- H. Asphalt Roofing Cement: ASTM D 4586, asbestos free, of consistency required for application.

2.4 FABRICATION, GENERAL

- A. General: Custom fabricate sheet metal flashing and trim to comply with recommendations in SMACNA's "Architectural Sheet Metal Manual" that apply to design, dimensions, geometry, metal thickness, and other characteristics of item indicated. Fabricate items at the shop to greatest extent possible.
 - 1. Fabricate sheet metal flashing and trim in thickness or weight needed to comply with performance requirements, but not less than that specified for each application and metal.
 - 2. Obtain field measurements for accurate fit before shop fabrication.
 - 3. Form sheet metal flashing and trim without excessive oil canning, buckling, and tool marks and true to line and levels indicated, with exposed edges folded back to form hems.
 - 4. Conceal fasteners and expansion provisions where possible. Exposed fasteners are not allowed on faces exposed to view.
- B. Fabrication Tolerances: Fabricate sheet metal flashing and trim that is capable of installation to tolerances specified in MCA's "Guide Specification for Residential Metal Roofing."
- C. Sealed Joints: Form nonexpansion but movable joints in metal to accommodate elastomeric sealant.
- D. Expansion Provisions: Where lapped expansion provisions cannot be used, form expansion joints of intermeshing hooked flanges, not less than 1 inch deep, filled with butyl sealant concealed within joints.
- E. Fabricate cleats and attachment devices from same material as accessory being anchored or from compatible, noncorrosive metal.
- F. Fabricate cleats and attachment devices of sizes as recommended by SMACNA's "Architectural Sheet Metal Manual" for application, but not less than thickness of metal being secured.
- G. Seams: Fabricate nonmoving seams with flat-lock seams. Tin edges to be seamed, form seams, and solder.
- H. Do not use graphite pencils to mark metal surfaces.

2.5 LOW-SLOPE ROOF AND ROOF DRAINAGE SHEET METAL FABRICATIONS

- A. Roof-Edge Flashing (Coping, Metal Edge, Scupper Boxes): Fabricate in minimum 96-inch-long, but not exceeding 10-foot-long, sections. Furnish with 6-inch-wide, joint cover plates.
 - 1. Joint Style: Butted with expansion space and 6" wide concealed backup plates.
 - 2. Fabricate from the following materials:
 - a. 0.050 inch Aluminum Sheet Metal

2.6 MISCELLANEOUS SHEET METAL FABRICATIONS

- A. Pitch Pockets and Scupper Box Sleeves: Fabricate continuous flashings in minimum 96-inch-long, but not exceeding 12-foot-long, sections, where indicated. Fabricate from the following materials:
 - 1. Copper: 16 oz./sq. ft.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, to verify actual locations, dimensions and other conditions affecting performance of the Work.
 - 1. Verify compliance with requirements for installation tolerances of substrates.
 - 2. Verify that substrate is sound, dry, smooth, clean, sloped for drainage, and securely anchored.
- B. For the record, prepare written report, endorsed by Installer, listing conditions detrimental to performance of the Work.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 UNDERLAYMENT INSTALLATION

- A. General: Install underlayment as indicated on Drawings as in areas described below.
- B. Felt Underlayment: Install felt underlayment with adhesive for temporary anchorage to minimize use of mechanical fasteners under sheet metal flashing and trim. Apply in shingle fashion to shed water, with lapped joints of not less than 2 inches.

3.3 INSTALLATION, GENERAL

- A. General: Anchor sheet metal flashing and trim and other components of the Work securely in place, with provisions for thermal and structural movement. Use fasteners, solder, welding rods, protective coatings, separators, sealants, and other miscellaneous items as required to complete sheet metal flashing and trim system.
 - 1. Install sheet metal flashing and trim true to line and levels indicated. Provide uniform, neat seams with minimum exposure of solder, welds, and sealant.
 - 2. Install sheet metal flashing and trim to fit substrates and to result in watertight performance. Verify shapes and dimensions of surfaces to be covered before fabricating sheet metal.
 - 3. Install exposed sheet metal flashing and trim without excessive oil canning, buckling, and tool marks.
 - 4. Install sealant tape where indicated.
 - 5. Torch cutting of sheet metal flashing and trim is not permitted.

6. Do not use graphite pencils to mark metal surfaces.
- B. Metal Protection: Where dissimilar metals will contact each other or corrosive substrates, protect against galvanic action by painting contact surfaces with bituminous coating or by other permanent separation as recommended by SMACNA.
 1. Underlayment: Where installing metal flashing directly on cementitious or wood substrates, install a course of felt underlayment and cover with a slip sheet or install a course of polyethylene sheet.
- C. Expansion Provisions: Provide for thermal expansion of exposed flashing and trim. Space movement joints at a maximum of 10 feet (3 m) with no joints allowed within 24 inches (600 mm) of corner or intersection. Where lapped expansion provisions cannot be used or would not be sufficiently watertight, form expansion joints of intermeshing hooked flanges, not less than 1 inch (25 mm) deep, filled with sealant concealed within joints.
- D. Fastener Sizes: Use fasteners of sizes that will penetrate not less than 1-1/4 inches for nails and not less than 3/4 inch for wood screws.
- E. Seal joints as shown and as required for watertight construction.
 1. Where sealant-filled joints are used, embed hooked flanges of joint members not less than 1 inch (25 mm) into sealant. Form joints to completely conceal sealant. When ambient temperature at time of installation is moderate, between 40 and 70 deg F (4 and 21 deg C), set joint members for 50 percent movement each way. Adjust setting proportionately for installation at higher ambient temperatures. Do not install sealant-type joints at temperatures below 40 deg F (4 deg C).
 2. Prepare joints and apply sealants to comply with requirements in Division 07 Section "Joint Sealants."
- F. Soldered Joints: Clean surfaces to be soldered, removing oils and foreign matter. Pre-tin edges of sheets to be soldered to a width of 1-1/2 inches (38 mm), except reduce pre-tinning where pre-tinned surface would show in completed Work.
 1. Do not use torches for soldering. Heat surfaces to receive solder and flow solder into joint. Fill joint completely. Completely remove flux and spatter from exposed surfaces.
 2. Copper Soldering: Tin edges of uncoated copper sheets using solder for copper.

3.4 ROOF FLASHING INSTALLATION

- A. General: Install sheet metal flashing and trim to comply with performance requirements, sheet metal manufacturer's written installation instructions, and SMACNA's "Architectural Sheet Metal Manual." Provide concealed fasteners where possible, set units true to line, and level as indicated. Install work with laps, joints, and seams that will be permanently watertight and weather resistant.
- B. Roof Edge Flashing and Coping: Anchor to resist uplift and outward forces according to recommendations in SMACNA's "Architectural Sheet Metal Manual" and as indicated. Interlock bottom edge of roof edge flashing with continuous cleat anchored to substrate at staggered 3-inch centers.

- C. Counterflashing: Coordinate installation of counterflashing with installation of base flashing. Insert counterflashing in reglets or receivers and fit tightly to base flashing. Extend counterflashing 4 inches over base flashing. Lap counterflashing joints a minimum of 4 inches and bed with sealant.
- D. Roof-Penetration Flashing: Coordinate installation of roof-penetration flashing with installation of roofing and other items penetrating roof. Seal with elastomeric sealant and clamp flashing to pipes that penetrate roof.

3.5 WALL AND CURB FLASHING INSTALLATION

- A. General: Install sheet metal wall flashing to intercept and exclude penetrating moisture according to SMACNA recommendations and as indicated. Coordinate installation of wall flashing with installation of wall-opening components such as windows, doors, and louvers.


3.6 CLEANING AND PROTECTION

- A. Clean exposed metal surfaces of substances that interfere with uniform oxidation and weathering.
- B. Clean and neutralize flux materials. Clean off excess solder.
- C. Clean off excess sealants.
- D. Remove temporary protective coverings and strippable films as sheet metal flashing and trim are installed unless otherwise indicated in manufacturer's written installation instructions. On completion of installation, remove unused materials and clean finished surfaces. Maintain in a clean condition during construction.
- E. Replace sheet metal flashing and trim that have been damaged or that have deteriorated beyond successful repair by finish touchup or similar minor repair procedures.

END OF SECTION 076200


CITY AUDITORIUM
ROOF REPLACEMENT
PROJECT

CITY OF DANVILLE
125 N Floyd St,
Danville, VA 24541



KEY PLAN

SCALE





No.	DATE	BY	Description

REVISIONS	
DRAWN BY	WL
APPROVED BY	RAB
CHECKED BY	RAB
DATE	2018.08.17
TITLE	

ROOF PLAN

PROJECT NO. 500

A1.01



STAGING, STORAGE, DUMPSTER, AND CRANE MAP
SCALE: NTS

GENERAL NOTES:

- GENERAL CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR VERIFICATION OF ALL ROOF DIMENSIONS INCLUDING SIZES AND LOCATIONS OF ALL EXISTING ROOF MOUNTED EQUIPMENT AND ACCESSORIES.
- IT IS THE GENERAL CONTRACTOR'S RESPONSIBILITY TO INSURE THAT THE ROOF STRUCTURE IS NOT OVERLOADED BY WEIGHTS OF CONSTRUCTION EQUIPMENT, MATERIALS, AND PERSONNEL DURING CONSTRUCTION.
- THE GENERAL CONTRACTOR SHALL CONFINE HIS OPERATIONS TO THE IMMEDIATE VICINITY OF THE WORK SITE AS DIRECTED BY THE OWNER/ARCHITECT AND SHALL ACCESS THE ROOF ONLY FROM THE OUTSIDE OF THE BUILDING AT AREAS DIRECTED BY OWNER/ARCHITECT (SEE NOTE 10 BELOW).
- GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTION OF COMPLETED ROOF SECTIONS DURING ADJACENT ROOF OPERATIONS.
 - DO NOT USE COMPLETED ROOF SECTIONS TO ACCESS ADJACENT ROOF AREAS.
 - DO NOT STORE MATERIALS IN COMPLETED ROOF SECTIONS
 - DO NOT STORE MORE THAN ONE DAYS MATERIALS ON EXISTING ROOF AREAS
- DURING CONSTRUCTION, GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTION OF THE BUILDING AND ITS CONTENTS FROM THE ELEMENTS AND SHALL PROVIDE TEMPORARY ROOF PROTECTION AND COVERING AS NECESSARY.
- GENERAL CONTRACTOR IS RESPONSIBLE TO PROPERLY FLASH ALL PLUMBING VENTS, CURBS, MECHANICAL/ELECTRICAL CONNECTIONS, ETC.
 - RAISE ALL PLUMBING VENTS A MINIMUM 12" ABOVE TOP OF THE NEW ROOF SYSTEM.
- GENERAL CONTRACTOR SHALL PROPERLY DISPOSE OF ALL DEBRIS OFF SITE, DAILY (INCLUDES ROOF & GROUNDS)
- GENERAL CONTRACTOR IS REQUIRED TO PROVIDE TEMPORARY TOILETS, WASH FACILITIES AND DRINKING WATER. CONSTRUCTION WORKERS WILL NOT BE ALLOWED TO USE THE FACILITIES IN THE BUILDING.
- GENERAL CONTRACTOR SHALL COMPLETELY REMOVE THE EXISTING ROOF SYSTEM & ALL FLASHINGS & ALL FLASHINGS TO THE EXISTING ROOF DECK.
 - ONLY REMOVE THAT PORTION OF EXISTING ROOF THAT CAN BE REPLACED IN ONE DAY.
 - PROPERLY DISPOSE OF ALL ROOFING DEBRIS DAILY.
 - PRROVIDE A WATERPROOF TIE-IN TO THE EXISTING ROOF MEMBRANE DAILY REGARDLESS OF FORCASTED WEATHER CONDITIONS.
- GENERAL CONTRACTOR SHALL ACCESS THE ROOF FROM SPRING STREET FOR REMOVAL OF ROOF DEBRIS AND DELIVERY OF NEW MATERIALS TO THE ROOF.
 - GENERAL CONTRACTOR STAGING, STORAGE AREA, AND DUMPSTER SHALL BE THE GRASS LOT ON THE CORNER OF FLOYD & HIGH STREET
 - GENERAL CONTRACTOR TO ROPE OFF STAGING & STORAGE AREA
 - SET UP CRANE ON SPRING STREET AND PROVIDE TRAFFIC CONTROL AS REQUIRED
 - GENERAL CONTRACTOR TO REPAIR ALL DAMAGES TO EXISTING PARKING LOT & SPRING STREET
- ASBESTOS ROOFING & FLASHINGS WERE REMOVED IN 1990 DURING THE LAST ROOF REPLACEMENT PROJECT. HOWEVER IF SUSPECT MATERIALS ARE ENCOUNTERED DURING ROOF REPLACEMENT OPERATIONS, STOP WORK IN THE AREA AND CONTACT CITY PROJECT MANAGER FOR TESTING OF SUSPECT MATERIAL. PROCEED WITH WORK ON OTHER ROOF AREAS.
- GENERAL CONTRACTOR SHALL COMPLETELY FINISH EACH ROOF SECTIONS (ROOFING, FLASHINGS, ETC.) PRIOR TO PROCEEDING WITH SUBSEQUENT ROOF SECTIONS.

ROOF NOTES:



DESCRIPTION	NOTES
ROOF SECTION 100 NEW 60 MIL REINFORCED EPDM MEMBRANE FULLY ADHERED	<ul style="list-style-type: none">COMPLETELY REMOVE THE EXISTING ROOF SYSTEM AND ALL FLASHINGS TO THE EXISTING ROOF DECK.REMOVE EXISTING METAL COPINGS, TERMINATION BARS, SCUPPER BOXES, AND COPPER THRU WALL SLEEVES, WOOD BLOCKING, ETC. <p><u>EXISTING ROOF COMPOSITION</u></p> <ul style="list-style-type: none">METAL DECK1/2" GYPSUM DRYWALL3/4" RIGID POLYISOCYANURATE INSULATION60 MIL EPDM MEMBRANE <p><u>NEW ROOF COMPOSITION</u></p> <ul style="list-style-type: none">METAL DECK4" RIGID INSULATION MECHANICALLY FASTENED TO METAL DECK60 MIL REINFORCED EPDM MEMBRANE FULLY ADHERED
ROOF SECTION 101 NEW 60 MIL REINFORCED EPDM MEMBRANE FULLY ADHERED	<ul style="list-style-type: none">COMPLETELY REMOVE THE EXISTING ROOF SYSTEM TO METAL DECK INCLUDING METAL TRIM AT PERIMETER <p><u>EXISTING ROOF COMPOSITION</u></p> <ul style="list-style-type: none">METAL DECKMETAL ROOFMODIFIED BITUMEN <p><u>NEW ROOF COMPOSITION</u></p> <ul style="list-style-type: none">METAL DECK4" RIGID INSULATION ADHERED TO METAL DECK60 MIL REINFORCED EPDM MEMBRANE FULLY ADHERED

NOTE: CONTRACTOR REQUIRED TO REMOVE ALL EXISTING INSULATION SCREWS PRIOR TO INSTALLATION OF NEW INSULATION SCREWS IN METAL DECK AREA

KEYED ROOF NOTES:

SYMBOL	DESCRIPTION	NOTES
①	SCUPPER BOX & DOWNSPOUTS (SB/DS)	<ul style="list-style-type: none">REMOVE EXISTING SCUPPER BOX & THRU WALL SLEEVEEXISTING DOWNSPOUT TO REMAINSEE DETAIL 2/A1.02 FOR NEW SCUPPER BOX
②	POWER VENT (PV) GRAVITY VENT (GV)	<ul style="list-style-type: none">RAISE EXISTING CURBS MINIMUM 8" ABOVE ROOF MEMBRANEFLASH CURB PER DETAIL 4/A1.02REINSTALL GV/PV
③	EXHAUST FAN (EF)	<ul style="list-style-type: none">COMPLETELY REMOVE EXISTING EF HOUSING (FRAME & SHEET METAL SIDING)INSTALL WOOD BLOCKING ON DECK TO RAISE ENTIRE UNIT MINIMUM 8"SECURE EF HOUSING TO WOOD BLOCKINGFLASH EF PER MANUFACTURERS RECOMMENDATIONS
④	VENT PIPE (VP)	<ul style="list-style-type: none">EXTEND VP MINIMUM 12" ABOVE ROOFPROPERLY FLASH PER ROOF MANUFACTURERS RECOMMENDATIONS
⑤	EXISTING CONDENSING UNIT	<ul style="list-style-type: none">REMOVE EXISTING ABANDONED CONDENSING UNIT & WOOD BLOCKINGREMOVE CONDUIT & DISCONNECT CONDENSING UNIT TO PENTHOUSEOWNER TO REMOVE WIRING & REFRIGERANT
⑥	OVER FLOW SCUPPER	<ul style="list-style-type: none">INSTALL 6" DIAMETER OVERFLOW SCUPPER PER DETAIL 3/A1.02

CITY AUDITORIUM
ROOF REPLACEMENT
PROJECT
CITY OF DANVILLE
125 N Floyd St.
Danville, VA 24541




No.	DATE	BY	Description

REVISIONS			


ROOF DETAILS

PROJECT NO. 500


A1.02




1 PARAPET WALL DETAIL
A1.02 SCALE: 1 1/2" 1'-0"




2 SCUPPER BOX DETAIL
A1.02 SCALE: 1 1/2" 1'-0"




3 OVERFLOW SCUPPER DETAIL
A1.02 SCALE: 1 1/2" 1'-0"




4 TYPICAL CURB DETAIL
A1.02 SCALE: 1 1/2" 1'-0"




5 FLASHING DETAIL
A1.02 SCALE: 3" 1'-0"



6 DETAIL
A1.02 SCALE: 3" 1'-0"



7 DETAIL
A1.02 SCALE: 3" 1'-0"



NOTE: DETAIL APPLIES TO ALL HORIZONTAL & VERTICAL FIELD FABRICATED LAPS
TYPICAL EPDM LAP DETAIL
SCALE: 3" 1'-0"

